

Chairman Ben Guttman  
Date Dec 20, 1994

Center of Section 25, Henrietta Township  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
JACKSON COUNTY  
RECORDED

28 DEC 94 9:55 A.M.

GERALD J. McDEVITT  
REGISTER OF DEEDS

For corners in	Located In:	Corner Code #
JACKSON (County)		
1. Public Land Survey	T <u>1S</u> R <u>1E</u>	<u>L-10</u>
	T _____ R _____	_____
	T _____ R _____	<u>SURVEY &amp;</u>
	T _____ R _____	<u>REMONUMENTATION</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>MAY 03 1995</u>
4. Lot No. _____, Recorded Plat _____		<u>COMMISSION</u>
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on December 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner not established in original government survey of 1825, nor subsequently by Bean in 1888. In 1988, D.A. Ankrom, L.S. #21265, established the corner at the intersection of the 1/4 lines per field notes on page 65 of Book S42 (on file at Sheridan Surveying Company) during Superconducting Super Collider surveys.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar with cap #21265. This corner was established in part, from corner "L-11" as recorded in Liber 4, Page 90. "L-11" was incorrectly reestablished in 1988, and as a result, iron #21265 is also incorrect, and is not utilized in this survey. Established corner at intersection of E-W and N-S 1/4 lines as defined by 1994 remonumentation corners. Set standard 60" aluminum pipe with Jackson County Remonumentation (JCR) cap. Corner is near the toe of the Westerly berm of a N-S drainage canal, in a marshy area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" x 60" aluminum pipe with JCR Aluminum Cap stamped "L.S. 29245, 1994, L-10."

N04°E	Capped iron #27456 (property corner)	153.86'
N71°E	Set Spike and Tag 29245 in North side of 17" Boxelder	42.13'
S80°E	Set Spike and Tag 29245 in South side of 20" Maple (clump)	56.02'
S39°E	Set Spike and Tag 29245 in Northeast side of 23" Cottonwood	78.00'
S85°W	Set Spike and Tag 29245 in South side of 17" Boxelder	208.66'
N83°W	Capped iron #21265 (unrecorded Center 1/4 corner)	5.14'
	North County Surveyor sign post	0.8'
	East Approximate West edge of N-S drainage canal	70'

Note: Bearings are magnetic.



Signed by David Erickson Date December 20, 1994

Surveyor's Michigan License No. 29245