

JACKSON COUNTY  
APPROVED LAND CORNER  
P.A. 343 of 1990

Witness Corner to  
Northwest Corner of Section 31, Henrietta Township

FEB 08 2000

Chairman [Signature]  
Date 12/23/99

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
JACKSON  
(County)

Located In:

Corner Code #



2141953  
Page: 1 of 1  
01/05/2000 09:14A  
L-1620 P-1112

1. Public Land Survey T      R       
T      R       
1a. Remonumentation "Other" code T 1S R 1E  
T      R
2. Property Controlling S 31 T 1S R 1E  
in Section S      T      R
3. Miscellaneous S      T      R       
Property in Sec. S      T      R

3  
(W.C. to A-11)

Register of Deeds Stamp & File Number

4. Lot No.      Recorded Plat       
5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on March 21, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The original survey of 1825 notes "Intersect W. Boundary In Lake." No corner was set and no falling was noted. In 1888, H.F. Bean noted "In Lake".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position falls in Malay Lake. Since no falling was noted for this corner, I believe the only way to establish this position is to intersect the Meridian with the North line of Section 31. Therefore, I re-established the position of this corner by intersecting the Principal Meridian line, between corners "M-10" and "M-11", T1S-R1W, as remonumented, with the North line of Section 31. The North line of Section 31 determined by extending the line between corners "B-11" and "C-11", T1S-R1E, as remonumented, to the Meridian. I then established a Witness Corner (WC) on the Meridian, 633.51 feet North of the calculated position of "A-11", in lake. Set a standard concrete monument on North side of Malay Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 4" diameter x 36" long concrete monument with Jackson County standard aluminum cap stamped "W.C. A-11, T1S-R1E, 1997, LS #29245".

N 10° E	Set nail & tag #29245, West side 10" Oak	9.73'
S 12° W	Set nail & tag #29245, East RR tie fence post	21.73'
N 61° W	Southwest corner of house foundation	170.39'
N 53° W	Southeast corner of house foundation	138.51'
South	County Surveyor sign post	1.0'
South	North edge of Malay Lake	187'
West	North-South fence	5'
East	Centerline of old North-South lane	8'
North	Corner "M-10" T1S-R1W as remonumented	1441.01'
South	Calculated position of corner "A-11", T1S-R1E, in lake	633.51'
South	Corner "M-11" T1S-R1W, as remonumented	1214.30'

NOTE: Bearings are magnetic

Note: This corner is being re-recorded to satisfy State of Michigan requirements. It is the same corner as recorded in Liber 1540, Page 140

Signed by David Erickson Date 12/23/99

Surveyor's Michigan License No. 29245

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

