

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>1</u> T. <u>1</u> S., R. <u>1</u> W.		<u>M-1, M-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u> T. <u>1</u> S., R. <u>1</u> W.		<u>M-1, M-2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, _____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-1 Set post
S 49 1/2° W 122 LINKS 24" Red Oak
N 54° W 127 LINKS 23" Elm

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-1 Found 3" dia. Solid clay mon. set by Bean in 1873. Replaced with 20" dia. concrete mon. with 2" Brass Cap.
M-2 Found 3" dia Solid Clay Mon. set by Bean in 1873. Replaced with 3" dia. concrete mon. with 1/2" iron rod in center.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 20" dia. concrete mon. with 2" dia. Brass Cap.
S 89° E 50.57' Thorn Apple North 56.19' 14" Triple Basswood
N 60° 27' 36" E 50.0' 12" dia. concrete mon. S 29° 43' 35" W 50.0' 12" dia. concrete mon.
M-2 3" dia concrete mon. with 1/2" iron rod
N 89° W 67.38' 24" Basswood West 66.00' 3/4" iron pipe
S 53° W 106.38' 10" Shag Hickory East 66.00' 1" iron pipe

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____