

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>1</u> T. <u>1</u> S., R. <u>1</u> W.		<u>K-1, K-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u> T. <u>1</u> S., R. <u>1</u> W.		<u>K-1, K-2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S., R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, D. Scott do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Sept. 25 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Sept. 25 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1** Found "T" shaped iron 2" below gravel & Peacock Road. Recovered with notes from Consumers Power Co. Jackson, Mich.
- K-2** Found 3/4" iron pipe 2" below gravel surface. Recovered with notes from Consumers Power Co. Jackson, Mich.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1** NW Corner Section 1, T1S, R1W
 West 32.92' 6" Black Walnut S28°W 91.17' 15" TWIN Oak
 N26°W 49.22' 5" Black Walnut S86°E 17.4' 2" diameter Iron Gate Post 5' High
- K-2** W 1/4 Corner Section 1, T1S, R1W
 N33°W 49.06' 10" Hickory S73°E 29.70' 12" Black Oak
 S48°W 40.56' 36" Black Oak N58°E 50.68' 18" Peanut Hickory

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12029 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____