

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>1</u> T. <u>1</u> S., R. <u>1</u> W.		<u>L-1, L-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u> T. <u>1</u> S., R. <u>1</u> W.		<u>L-1, L-3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, D. Scott do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Oct. 18 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Oct. 18 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

L-1 Set 1/2 mi post
 White Oak 7" N68°E. 40 LINKS
 Dogwood 9" N73°W 32 LINKS

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L-1 Found 3/4" pinched iron pipe 2" below surface and 1' West of
 of Road. Recovered with notes from Polaris Engineering Inc. Lansing, Mi.
 This corner recorded by Polaris Engineering Inc.

L-3 Found R.R. spike 1.0' West of & Cooper Road. Recovered with
 notes from Consumers Powers Co. Jackson, Mich

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 NW4 Corner Section 1, T1S, R1W
 S52°W 20.58' 20" Oak N85°W 17.41' 18" Hickory
 S75°E 25.73' 24" Oak

L-3 SW4 Corner Section 1, T1S, R1W
 S89°W 21.80' Fence Corner Post S40°W 41.62' 7" Black Cherry
 N22°W 55.46' 8" Hickory S48°E 92.31' Power Pole

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12029 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____