

M-1 T1S R2W
PART A CONTINUED

2. IN NOVEMBER 1885 J. HOLCROFT REPORTED "FOUND CORNER SET BY H.F. BEAN FOR RIVES WHICH IS THE SAME FOR TOMPKINS,; WITNESS FOR TOMPKINS." HE ALSO RECORDED TWO WITNESSES:

ELM 15 S5½e 519 (342.5')
W. OAK 12 S86½W 501 (330.7')

3. CONSUMERS POWER COMPANY WITNESS SHEET
SET "T" IRON IN LINE WITH FENCE TO NORTH

ROAD SIGN S47°E 54.1'
FENCE CORNER S45°E 53.6'
TWIN MAPLE N55°E 45.9'
R.W. KELLER FB 1069 1-71

4. RONNIE M. LESTER LS 18998 RECORDED CORNER IN LIBER 6 PAGE 158 INGHAM COUNTY RECORDS AS A-13 LESLIE TOWNSHIP WHICH IT IS COMMON TO; HE REPORTED IN HIS LCRC "EXCAVATED 8' X 10' HOLE TO AN AVERAGE DEPTH OF 4' AT INTERSECTION OF BASELINE RD. AND BERRYVILLE RD. AND ON A FENCE LINE TO NORTH. FOUND ½" BAR 1" BELOW SURFACE IN LINE WITH WITH FENCE TO NORTH AS CALLED FOR IN CONSUMERS POWER NOTES. EVIDENCE FOUND CONSIDERED INCONCLUSIVE. EXCAVATED A SECOND HOLE 8' X 13' TO AN AVERAGE DEPTH OF 3.0' TO THE SOUTH OF THE CENTERLINE OF BASELINE RD. WEST OF THE CENTERLINE OF BERRYVILLE RD. ON A FENCE LINE NORTH. FOUND FIRE CLAY + 0.8 BELOW SURFACE WITH BRICK OR CLAY TILE BENEATH + 3' WEST OF THE FENCELINE NORTH, + 2' SOUTH OF CENTERLINE BASELINE RD., +5' WEST OF THE CENTERLINE BERRYVILLE RD. ACCEPTED FIRE CLAY AS CORNER. REPLACED WITH 4" X 36" CONCRETE MONUMENT WITH ½" X 38" REROD AND CAP #18998.

NAIL & TAG, #18998, WEST SIDE 18" OAK, SSE, 100.39'

TOP CENTER OF FENCE POST, SE, 49.70'

NAIL & TAG, #18998, SOUTHEAST SIDE 8" TWIN WILD CHERRY, NE, 39.94'

NAIL & TAG, #18998, SOUTHEAST SIDE 8" TWIN OAK, NE, 52.28'