

Chief Surveyor Dean C. Fulkerson
 Date August 14, 1999

SW CORNER SECTION 6
 RIVES TOWNSHIP
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 REMONUMENTATION

MAR 18 2000

For corners in

JACKSON Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 1S R 1W _____ A-3
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____



2138086
 Page: 1 of 1
 11/24/1999 02:42P
 L-1618 P-25

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID L. CLIFFORD, in a field survey on DEC. 20, 1993 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 POST SET IN ORIGINAL GOVERNMENT SURVEY BY HERVEY PARKE, DEPUTY SURVEYOR ON MARCH 20, 1825 WITH THE STATEMENT "INTERSECTED RANGE LINE 93 LKS (61.4') NORTH OF CORNER" AND TWO BEARING TREES RECORDED: W. OAK 21 S60E 32 (21.1') AND W. OAK 24 N50E 45 (29.7').
 BETWEEN MAY AND JULY, 1885. H.F. BEAN REPORTED "FOUND POST AND ONE WITNESS AND ONE WITNESS FOR TOMPKINS CORNER" AND RECORDED TWO WITNESSES: B. WALNUT 12 N391/2W 89 (58.74') AND HICKORY S51W 159 (104.94').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND FIRECLAY POST IN VERY GOOD CONDITION AT GROUND SURFACE IN NORTH-SOUTH FENCE LINE. DID NOT FIND ANY EVIDENCE OF THE GLO OR BEAN WITNESS TREES. ACCEPTED FIRECLAY AS MARKER SET BY BEAN AT CORNER POINT. REMOVED FIRECLAY POST AND SET CONCRETE MONUMENT WITH ALUMINUM CAP IN ITS PLACE. TRAVERSED TOWNSHIP LINE IN DECEMBER 1997 AND FOUND MONUMENT WAS ON STANDARD LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-3 T1S R1W
 4" X 36" CONCRETE MONUMENT WITH 1/2" X 36" REBAR AND JACKSON CO. STANDARD CAP STAMPED LS 28409
 N87°E, 8" CHERRY, 1.23', 20D SPIKE AND TAG # 28409 IN NORTH SIDE
 S02°W, 33" HICKORY, 23.73', 20D SPIKE AND TAG #28409 IN WEST SIDE
 S33°W, 38" OAK, 64.50', 20D SPIKE AND TAG #28409 IN NW SIDE
 N60°W, 7" HICKORY, 40.00', 20D SPIKE AND TAG #28409 IN NW SIDE
 SOUTH, STANDARD JACKSON COUNTY CONCRETE MONUMENT AT M-3, T1S, R2W, 60.30'
 SURVEY MARKER SIGN POST, SOUTH, 1.0'

Signed by David Clifford

Date MARCH 24, 1999

Surveyor's Michigan License No. 25837

