

8-13-97

SURVEY & REMONUMENTATION

NOV 03 1999

JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1990

Chairman David L. Clifford
Date AUG. 13, 1997

WEST 1/4 CORNER SECTION 18
RIVES TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

| | | |
|------------------------------------|--|---------------|
| JACKSON | Located in: | Corner Code # |
| (County) | | |
| RIVES TOWNSHIP | | |
| 1. Public Land Survey | T <u>1S</u> R <u>1W</u> | <u>A-6</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

#2057142
Liber 1558 Page 537
Page 1 of 1
Jackson Co., MI
Recorded
12/29/1997 10:27A
Mindy Reilly
Register of Deeds

Register of Deeds Stamp & File Number

4. Lct No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on APRIL 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
- MONUMENT NOT SET IN ORIGINAL GLO SURVEY.
 - CONSUMERS POWER COMPANY USED CORNER AND STATED THEY USED IRON PIPE AND RECORDED 2 WITNESSES:
8" BLACK WALNUT 28.4'
12" BLACK WALNUT 35.80' S30W
 - ROAD COMMISSION USED CORNER AND LISTED 4 WITNESSES:
B. WALNUT 8" SOUTH 42.6'
B. WALNUT 12" S30W 54.3'
8" BLACK WALNUT 28.4'
12" BLACK WALNUT S30W 45.3'
 - SURVEYORS WORKING ON THE SUPER CONDUCTING SUPER COLLIDER SURVEY TRAVERSED TO CORNER IN JUNE 1988. MONUMENTATION USED WAS 1" SOLID BAR IN MONUMENT BOX.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1" SOLID BAR IN MONUMENT BOX 21.1' NORTH OF M-6 TOMPKINS 1' SOUTH OF NORTH EDGE OF WOOD ROAD. EXCAVATED THROUGH BOX AND FOUND NO FURTHER EVIDENCE OF A HISTORICAL NATURE. COMPARISON OF A SUPER CONDUCTING SUPER COLLIDER TRAVERSE INDICATED THAT BAR WAS ON STANDARD LINE AND MEASURED 2677.18' TO A-5 AND 2673.22' TO A-7. CONSUMERS POWER COMPANY WITNESSES ARE TO A 1/2" PINCH PIPE 12.6' SOUTH OF CORNER. ACCEPTED 1" BAR AS PERPETUATION OF CORNER AND REPLACED WITH CAST IRON MONUMENT.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-6 T1S R1W
4" X 30" CAST IRON HARRISON MONUMENT WITH BRASS CAP STAMPED JACKSON COUNTY LS 25837.
- | | |
|------------------|--|
| NAZ 4° 6.2' | SURVEY MARKER SIGN POST |
| NAZ 123° 113.39' | 60D IN N.E. SIDE 35" WHITE PINE |
| NAZ 139° 76.10' | NAIL AND TAG 28409 W. SIDE 37" OAK |
| NAZ 184° 21.10' | M-6 (STANDARD CONC. MONUMENT) |
| NAZ 186° 41.17' | NAIL AND TAG 28409 IN W. SIDE 29" WALNUT |
| NAZ 219° 50.40' | 60D SPIKE IN S.E. SIDE 22" OAK |
| NAZ 317° 91.91' | NAIL AND TAG 28409 IN W. SIDE POWER POLE |

Signed by David L. Clifford Date AUGUST 11, 1997
Surveyor's Michigan License No. 25837

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1976

REVISED JAN, 1983
REVISED OCT., 1996

