

JACKSON COUNTY
 APPROVED LAND CORNER

P.A. 845 of 1990

Commissioner Dean K. Subbinal

Date AUG. 13, 1997

NORTHWEST CORNER SECTION 19
 RIVES TOWNSHIP
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2057143
 Liber 1558 Page 538
 Page 1 of 1
 Jackson Co., MI
 Recorded
 12/29/1997 10:27A
 Mindy Reilly
 Register of Deeds

For corners in

JACKSON Located In: _____
 (County)

Corner Code # **SURVEY &
 REMONUMENTATION**

SEP 8 1999

SECTION

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>1S</u> R <u>1W</u> | <u>A-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on APRIL 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. HERVEY PARKE D.S. SET MONUMENT IN ORIGINAL GLO SURVEY IN MARCH 1825.

W. OAK 14 N76-1/2E 48(31.7')
 D.O. 10 S81W 23(15.2')

2. H. F. BEAN USED CORNER IN 1885 AS " POST STANDING AND ONE WITNESS STUMP AND ONE WITNESS FOR TOMPKINS CORNER. RECORDED TWO NEW WITNESSES AS:

W. OAK 10 S2E 227(149.8')
 BURR OAK 16 N36-1/2W 66(43.6')

3. ANTHONY P. KURZY LS 14326 USED CORNER IN JULY 1973 AND RECORDED IT IN L 2 PG 235 OF JACKSON COUNTY RECORD OF CORNERS AS " FIRE CLAY" AND RECORDED 3 WITNESSES:

14" OAK S87°W 22.25'
 13" OAK NORTH 22.70'
 FIRE CLAY(M-7 T1S R2W) SOUTH 14.3'

4. THIS SURVEYOR USED FIRE CLAY AS CORNER WHILE WORKING ON SUPER CONDUCTING SUPER COLLIDER SURVEY AND TOOK THE FOLLOWING WITNESSES:

16D NAIL IN 18" OAK NORTH 22.45'
 16D NAIL IN 30" OAK SOUTH 52.60'
 16D NAIL IN 15" OAK S.W. 22.25'
 16D ANIL IN 8" WILLOW EAST 39.2'
 FIRE CLAY(M-7 T1S R2W) SOUTH 14.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND FIRE CLAY 14.3' NORTH OF M-7 TOMPKINS AS I HAD IN 1988. ACCEPTED FIRE CLAY AS PERPETUATION OF CORNER. LEFT FIRE CLAY IN PLACE AND SET STANDARD CONC. MONUMENT 0.5' WEST AT AMMENDED CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 T1S R1W

36" X 4" CONC. MONUMENT AND 3" ALUMINUM CAP STAMPED JACKSON COUNTY REMONUMENTATION LS 25837.

- NAZ 166° 19.45' ACCOLADE NAIL AND TAG IN N.E. SIDE 8" MAPLE
- NAZ 184° 17.4' SURVEY MARKER SIGN POST
- NAZ 184° 14.30' STANDARD CONC. MONUMENT (M-7 T1S R2W)
- NAZ 184° 17.05' ACCOLADE NAIL AND TAG E. SIDE R.R. TIE FENCE POST
- NAZ 191° 52.50' 60D SPIKE IN E. SIDE 30" OAK
- NAZ 237° 21.32' 60D SPIKE IN N. SIDE 19" OAK
- NAZ 358° 22.40' 60D SPIKE IN E. SIDE 18" OAK

Signed by David L. Clifford
 Surveyor's Michigan License No. 25837

Date AUGUST 11, 1997

