

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Jackson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1S</u> R <u>1W</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 345 of 1990**  
 Chairman Dean Hubbard  
 Date Oct. 13, 1994  
**Register of Deeds Stamp & File Number**

I, Alan L. Schepelman in a field survey on September 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

**HERVEY** POST SET IN ORIGINAL GOVERNMENT SURVEY  
**PARKE** ELM 24, N12°W, 218 LINKS (143.9')  
 1825 W. OAK 24, S01°W, 380 LINKS (250.8')

**H.F. BEAN** POST GONE, FOUND ONE WITNESS  
 1885 ELM 4, S88°W, 15 LINKS (9.9')  
 W. OAK 36, N14°W, 261 LINKS (172.3')

\$ 2.00 REMONUMENTATION  
 \$ 7.00 CORNER REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BROKEN FIRECLAY (BOTTOM 1')  
 WITH 3/4" X 18" PINCHED PIPE ON NORTH SIDE  
 ONE PIECE OF CLAY TILE WAS FOUND  
 POINT IS IN LINE WITH A FENCE TO THE NORTH  
 POINT IS ON WESTERLY SIDE OF SWAMP

STATE OF MICHIGAN  
 JACKSON COUNTY  
 RECORDED  
 27 DEC 94 12:09 P.M.

THE FIRECLAY WAS ACCEPTED AS A PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER AS REMONUMENTED IN 1885. SET 1" X 60" ALUMINUM PIPE WITH A STANDARD JACKSON COUNTY REMONUMENTATION CAP.

GERALD J. McDEVITT  
 REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" x 60" ALUM. PIPE WITH JACKSON COUNTY REMONUMENTATION CAP STAMPED LS35998. BURIED PIECE OF FIRECLAY ON N. SIDE.  
 20d NAIL & RAISED SHINER ON W. SIDE 28" OAK N05°W 26.58'  
 20d NAIL & RAISED SHINER ON W. SIDE 18" MAPLE N15°E 13.86'  
 20d NAIL & RAISED SHINER ON N. SIDE DEL 10" MAPLE S85°E 12.60'  
 20d NAIL & RAISED SHINER ON E. SIDE 15" MAPLE S15°W 35.31'  
 20d NAIL & RAISED SHINER ON SE SIDE 8" ASH S65°W 33.10'  
 20d NAIL & RAISED SHINER ON S. SIDE 8" ASH N60°W 10.83'



Signed by Alan L. Schepelman Date 10/03/94  
 Surveyor's Michigan License No. 35998