

1/4 Corner between Section 28 and 29

Set brass 1/4 corner cap on 1" pipe.
3" below road surface at road centerline.
N. 57° 30' E., 55.73', 7" Oak, horizontal spike.
N. 56° 30' W., 51.74', 18" Oak, horizontal spike
S. 76° 30' E., 102.75', 10" Elm, South of 5,
horizontal spike.

Section Corner common to Sec. 28, 29, 32 and 33.

Set 7" steel drag tooth, at centerline of road.
1/2" below road surface.
Over center of 24" C.M.P.
N. 76° W., 34.67', 8" Elm, horizontal spike.
S. 88° 30' E., 48.17', 12 Ash, horizontal spike.

Very truly yours,

Hathaway J. Hanes, P.E., In Charge
Engineering and Architecture

WLP

W. Lee Paddison
Engineering and Architecture

WLP:gep

CC: Richard Gutekunst