

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Jackson
(County)

Located In:

Corner Code ~~##~~

- | | | | |
|---------------------------------------|-------------|-------------|-------------|
| 1. Public Land Survey | T <u>1S</u> | R <u>2E</u> | <u>L-12</u> |
| | T <u>1S</u> | R <u>2E</u> | <u>M-12</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

Register of Deeds Stamp & File Number

I, Craig A. Eckfeld, in a field survey on November 04, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 18 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

L-12
 Center of Section 36
 (No witnesses available)

M-12
 East 1/4 Corner of Section 36
 Hickory 10" S 70 deg. W 78 links
 White Oak 14" N 29 deg. W 183 links
 Government Notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-12
 Set 1"x 3"± Iron Pipe
 on intersection of 1/4 lines

M-12
 60-D in 6" Hickory S 80 deg. E 0.81
 60-D in Twin 12" Oak S 07 deg. W 18.46
 60-D in Twin 24" Oak S 55 deg. W 48.60
 60-D in 8" Hickory N 08 deg. W 26.96
 3/4 x 36" Pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-12
 Set 1' x 3' Iron Pipe
 Twin 10" Hickory N 20 deg. E 11.70 to nail
 18" Hickory S 85 deg. E 24.40 to nail
 20" Elm S 30 deg. E 21.90 to nail
 14" Ash W'ly 15.80 to nail

M-12
 Found 3/4" Iron Pipe (Cap #24621)
 12'± East of east edge of gravel road
 12" Stump E'ly 0.81 to nail
 12" Elm S 60 deg. E 42.23 to nail
 12" Sassafras N 50 deg. E 28.96 to nail
 10" Oak N 20 deg. E 19.12 to nail
 Twin 32" Oak S 55 deg. W 48.57 to nail

Signed by _____ Date November 9, 1992

Surveyor's Michigan License No. 33135