

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Jackson</u> <small>(County)</small>	Located In:	Corner Code $\neq$
1. Public Land Survey	T <u>1S</u> R <u>2E</u>	<u>K-11</u>
	T <u>1S</u> R <u>2E</u>	<u>K-12</u>
	T <u>1S</u> R <u>2E</u>	<u>L-11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**Register of Deeds Stamp & File Number**

I, Craig A. Eckfeld, in a field survey on November 04, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |   |                                 |                                 |
|---|---------------------------------|---------------------------------|
| K-11<br>NW Corner Section 36<br>Black Oak 8" S12deg.E 26 links<br>White Oak 36" N39 1/2deg.E 32 links<br>Government Notes | K-12<br>W 1/4 Corner Section 36 | L-11<br>N 1/4 Corner Section 36 |
|---|---------------------------------|---------------------------------|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |   |   |   |
|---|---|---|
| K-11<br>60-D in 7" Cherry N20deg.E 19.83<br>60-D in 52" Oak S12deg.E 16.78<br>60-D in 24" Oak N60deg.W 1.85<br>60-D in 8" Cherry N15deg.W 24.97<br>1" X 24" Iron Pipe | K-12<br>60-D in 15" Oak N04deg.E 30.44<br>60-D in 20" Oak N75deg.E 12.11<br>60-D in 10" Ash S35deg.E 20.96<br>60-D in 12" Cherry S18deg.W 66.75<br>3/4" X 36" Pipe at Anchor Post | L-11<br>60-D in 24" Oak N30deg.E 313.46<br>60-D in 18" Oak S50deg.E 380.37<br>60-D in 36" Oak S00deg.W 275.41<br>60-D in 15" Oak N40deg.W 312.81<br>Concrete Monument |
|---|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |   |
|--|---|---|
| K-11<br>Found 1" Iron Pipe from assessories<br>in Section B<br>5± E on N-S Fence Line<br>7" Cherry N20deg.E 19.75 to nail<br>52" Oak S12deg.E 16.75 to nail<br>24" Oak N60deg.W 1.85 to nail<br>8" Cherry N15deg.W 24.97 to nail | K-12<br>Found 3/4" Iron Pipe<br>20" Oak N04deg.E 30.44 to nail<br>30" Oak N75deg.E 12.11 to nail<br>12" Elm S35deg.E 20.96 to nail<br>18" Cherry S18deg.W 66.75 to nail<br>6" Maple S75deg.E 6.95 to nail | L-11<br>Found Concrete Monument<br>36" Oak N30deg.E 313.46 to nail<br>F.I.P. N'y 254.00<br>24" Oak N40deg.W 312.81 to nail<br>48" Oak S'y 275.41 to nail<br>30" Oak S50deg.E 380.37 to nail |
|--|---|---|

Signed by \_\_\_\_\_ Date November 11, 1992

Surveyor's Michigan License No. 33135