## LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -: LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY 16 T. 2 S., R. 2 E.	E-5, E-6
2. PROPERTY CONTROLL- N. E. ING IN SECTION T. T. S., R. W.	
3. MISCELLANEOUS N. E. PROPERTY IN SECTION. , T	i i
•	
4. LOT NO, RECORDED PLAT	
5. PRIVATE CLAIMS	REGISTER OF DEEDS STAMP AND FILING NUMBER
I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 19 77 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:	
A. Description of original monument and accessories and/or s	subsequent restoration:
E-5 \$75°30'M, 12.19', 18" Oak \$20°E, 8.32', 16" Oak NO7°E, 55.18', SM Cor. House West, 120.0', E road \$75°E, 13.31', 11" Oak	E-6 19" Triple W. Cherry, S23°W, 21.79' 11" W. Cherry, S09°W, 38.35' At North side of Rail-road tie anchor post.
<ul> <li>B. Description of corner evidence found and/or method applied</li> <li>E-5</li> <li>Found 1" pipe flanged out to 3"</li> </ul>	ed in restoring or re-establishing corner:  E-6  Found ½" pipe North side of rail-road tie anchor post.
C. Description of monument for corner and accessories establing  E-5  \$75°30'\( 12.19', 18''\) Oak \$20°E, 8.82', 16'' Oak \$07°E, 55.18', \$\( \text{SW} \) cor. house \$75°E, 13.31', 11'' Oak \$Placed \( \frac{1}{2}'' \) pipe with plastic cap	E-6 S03°W, 68.20', 14" Hickory S12°W, 38.22', 15" B. Cherry S36°W, 42.90', 13" Oak S42°W, 21.40', 12" Triple Cherry South, 0.5', center fence post
#18655 Inside 1" pipe.	placed plastic cap #19655 in pipe.
SURVEYOR'S MICHIGAN REGISTRATION NO.	(SEAL)
FOR STATE AND UNITED STATES AGENCIES:	e de seul es complete en la complete de la complete del la complete de la complet
	DATE
APEROVED AND SHONED DE JORAL ABISAL	DATE  DATE 11-22-77  (SEAL)
*****	

\_\_\_\_\_