

Chairman David E. Erickson  
 Date Mar. 11, 1998

Southwest Corner of Section 18, Waterloo Township

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
JACKSON  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T1S R2E

A-7

T R

T R

T R

2. Property Controlling  
 in Section

S T R

S T R

3. Miscellaneous  
 Property in Sec.

S T R

S T R

SURVEY &  
 REMONUMENTATION

SEP 16 1998

#2064440  
 Liber 1563 Page 986  
 Page 1 of 1  
 Jackson Co., MI  
 Recorded  
 03/12/1998 12:00P  
 Mindy Reilly  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_ SECTION \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on August 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In 1825, J. Wampler - Deputy Surveyor, indicates "Intersected W. Boundary 5 lks. S. of post. Set post cor Sec. 18+19" and list two witnesses: "Tamarack 6, S22 1/2°E, 95" (62.70') and "W. Oak 22, N26 1/2°E, 249" (164.34').

In 1988, R.L. Enger - LS #28409, recorded the corner as "Established corner point on East boundary of T1S, R1E at 3.30 feet South of M-7, T1S, R1E. Set 1/2" bar and cap #28409 to monument corner point." and recorded four witnesses: "North, 3.30', 3/4" pipe in monument box (M-7, T1S, R1E); 318° NAZ 72.7', Nail and shiner in East side of Utility Pole; 245° NAZ, 56.9', Nail and shiner in North side of Utility Pole; 13° NAZ 161.8', Nail and shiner in West root of 40" Oak; 57° NAZ, 144.9' Nail and shiner in South side of 12" willow" per Land Corner Recordation Certificate (LCRC) recorded in Liber 4, Page 139.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron as set by Enger. Accepted iron as a careful and faithful re-establishment of the corner as monumented by Enger. Iron is on the Town Line. Iron is 3.11 feet South of M-7, not 3.30 feet due to found fireclay at M-7 not being directly below surface pipe. Set a standard Harrison cast iron monument at location of found iron. No backhoe search conducted.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 30" Harrison cast iron monument with cap stamped "#29245".

N 07° E	Set nail and tag #29245, West side 40" Oak	163.28'
S 63° W	Set nail and tag #29245, South side power pole	57.02'
N 46° W	Set nail and tag #29245, Northeast side power pole	72.76'
North	Harrison monument (M-7, T1S-R1E)	3.11'
N 87° E	County Surveyor sign post	19.5'

NOTE: Bearings are magnetic



Signed by David E. Erickson Date 3-11-98

Surveyor's Michigan License No. 29245