

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

S.W. Section 12 Tompkins Twp.

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 1 ^{N.} S. R. 2 ^{W.}	K-5
2. PROPERTY CONTROLLING IN SECTION _____	. T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	. T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____	RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____		

SEP 1 PAGE 479-
RECORDED
DEC 27 12 33 PM '72
REGISTER OF DEEDS
OSHTON COUNTY, MICH.
James H. DeWolfe
REGISTER OF DEEDS STAMP AND FILING NUMBER

RICHARD E. GUTENKUNST, RLS do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on MAY 19 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Maple 26 - N87½°W - 19 links - 12.54'
Ash 28 - N75°E - 25 links - 16.50'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Maple 12 - S72½°E - 32 links - 21.12'
Ash 15 - S 9½°W - 11½ links - 7.59'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Pound fire clay with C. P. Co. "T" iron on east side. Set ¾ x 5' capped iron on West side in swamp. No fences.
Sly. - double oak - 35.78'
Wly. - 15" maple - 10.84'
Nly. - 12" maple - 32.13'
Ely. 20" maple - 47.86'

SIGNED BY *Richard E. Gutenkunst* DATE May 19, 1972
SURVEYOR'S MICHIGAN REGISTRATION NO. 7863

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
APPROVED AND SIGNED BY _____ DATE _____

