

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

1/2 Post Section 12 Township 47N,

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>1</u> S., R. <u>2</u> E.	<u>K-4</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ S., R. _____ E.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S., R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

SEP 1 1972

RECORDED

SEP 27 12 30 PM '72

REGISTER OF DEEDS
MICHIGAN COUNTY, MICH.
James H. Alderton
REGISTER OF DEEDS STAMP AND
FILING NUMBER

RICHARD E. GUTENUNST, RLS do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in field survey on July 19-27 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

W. Oak 11 - S89 1/2° E - 35 links - 23.10'
Els 11 - S79° W - 45 links - 30.36'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Hickory 11 - S24° E - 32 1/2 links - 21.45'
B. Oak 14 - N30 1/2° E - 30 links - 19.80'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Fire Clay 12" below surface on east side old corner Post. Found C. P. Co. "T" iron 3.1' West of Fire Clay. Set 3/4 x 1 1/8" iron on SE side of Fire Clay. capped
Witness to iron
Sly. RR Post 3.9'
S85° ± E - 6" W. oak - 55.89'
S20° ± E - 6" hickory - 55.07'
West - 12" Ash - 30.41'


SIGNED BY *Richard E. Gutenunst* DATE SEP 24, 1972

SURVEYOR'S MICHIGAN REGISTRATION NO. 7863

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____