

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SE Corner                      Section 12                      Tompkins Township

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>1</u> S., R. <u>2</u> W.	<u>M-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Richard E. Gutekunst, RLS, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 29, 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

W. Oak 30	N 12½ W	193 links	127.38
W. Oak 30	S 58 W	208 links	137.28
Br. Oak 12	S ¾ E	187 ¾ links	123.92
Y. Oak 12	N 41 ¾ E	50½ links	33.33

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Fireclay at East side of old Corner Post  
Set ¾ x 18" Capped Iron on Northwest side

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

N 25°± E	24" Oak	3.68'	
N 45°± E	20" Db1 Oak	13.44'	
West	24" Oak	36.9'	
North	SWC, Sec. 7, T1S, R1W		31.34'

SIGNED BY Richard E. Gutekunst                      DATE April 26, 1976

SURVEYOR'S MICHIGAN REGISTRATION NO. 7863

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

