

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

S $\frac{1}{4}$  Post Section 12 Tompkins Township

FOR CORNERS OF --	LOCATED IN --			CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 1	X. S., R. 2	K. W.	L-5
2. PROPERTY CONTROLLING IN SECTION	T. _____	N. S., R. _____	E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____	N. S., R. _____	E. W.	
4. LOT NO. _____, RECORDED PLAT _____				
5. PRIVATE CLAIMS _____				

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Richard E. Gutekunst, RLS, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 29, 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

W. Oak 30	S 26 E	20 links	13.20'
W. Oak 22	N 23 W	32 links	21.12'
Maple 15	N 21 $\frac{1}{2}$ E	108 $\frac{1}{2}$ links	71.45'
Y. Oak 15	N 42 W	192 links	126.72'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Fireclay 22" below surface  
Set 3/4 x 18" Capped Iron on top of Fireclay and also Iron on North side, 12" below gravel surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

N W	12" Oak	30.03'
S E	Triple Ash	152.62'
N 88 $\pm$ E	6" Oak	53.59'
Northerly	5" Oak	51.38'

SIGNED BY Richard E. Gutekunst DATE April 26, 1976

SURVEYOR'S MICHIGAN REGISTRATION NO. 7863

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

