

JACKSON COUNTY
 APRIL 14, 1999
 Surveyor *Ronald L. Enger*

WEST 1/4 CORNER SECTION 6
 TOMPKINS TOWNSHIP
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 REMONUMENTATION

MAR 18 2000

SECTION

For corners in

JACKSON Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T 1S R 2W _____ A-2 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____



2138089
 Page: 1 of 1
 11/24/1999 02:42F
 L-1518 P-28

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RONALD L. ENGER, in a field survey on APRIL 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- POST NOT SET IN ORIGINAL SURVEY.
- GLO NOTES FOR M-2, T1S, R3W, STATE ORIGINAL POST SET BY JOSEPH WAMPLER, D.S. IN JANUARY, 1824: TAM, 9", S28W, 5; B.O., 11", N40 1/2W 36 1/2
- IN MAY 1886 JOHN HOLCROFT REPORTED: "FOUND STAKE SET BY CROUL WHEN COUNTY SURVEYOR, WITH BRICK AROUND IT 103 LKS (68.0') SOUTH OF SPRINGPORT 1/4 POST. SET FIRECLAY POST AND TALL STAKE ALONG SIDE OF IT SO AS TO EASILY FIND IT." HE RECORDED TWO WITNESSES AS:
 TAMARACK 6 N2°E 34 1/2 (22.8')
 MAPLE 6 S86 1/4°W 13 1/2 (8.9')
- CONSUMERS POWER COMPANY DRAWING SHOWS THE CORNER AS A COMPUTED LOCATION. NO MENTION OF MONUMENT AT THE CORNER OR ANY WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED IN GENERAL LOCATION OF CORNER ALONG REMNANTS OF NORTH-SOUTH FENCE. AFTER MUCH SEARCHING, FOUND MINUTE REMNANTS OF FENCE COMING FROM THE WEST. TRACED REMNANTS TO NORTH-SOUTH FENCE; POSITION FALLS ON EXTREMELY LARGE STONE. TAPED 68.0 FEET SOUTH FROM THIS POSITION INTO SWAMP. FOUND FIRECLAY POST 0.2 FEET ABOVE WATER SURFACE AND SURROUNDED BY STONES. ACCEPTED FIRECLAY AS CORNER PERPETUATED BY HOLCROFT. SET 4" X 36" CONCRETE MONUMENT WITH JACKSON COUNTY ALUMINUM CAP IN PLACE OF FIRECLAY. LEFT FIRECLAY ON NORTH SIDE OF CONCRETE MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-2 T1S R2W
 4" X 36" CONCRETE MONUMENT AND JACKSON COUNTY ALUMINUM CAP STAMPED 44268
- | | | |
|---------------------------------------|-----------|--------|
| NAIL & TAG (PS 28409) N SIDE 4" ELM | NAZ. 140° | 7.63' |
| NAIL & TAG (PS 28409) W SIDE 6" ELM | NAZ. 196° | 19.79' |
| NAIL & TAG (PS 28409) NW SIDE 20" OAK | NAZ. 300° | 38.65' |
| NAIL & TAG (PS 28409) N SIDE 6" ELM | NAZ. 304° | 15.55' |
| CONCRETE MONUMENT M-2 T1S, R3W | NAZ. 0° | 66.00' |
| SURVEY MARKER SIGN POST | NAZ. 0° | |



Signed by Ronald L. Enger
 Surveyor's Michigan License No. 28409

Date APRIL 14, 1999