

JACKSON COUNTY
 APPROVED LAND CORNER
 P.A. 345 of 1999
 Chairman *[Signature]*
 Date 12-11-96

CENTER, SECTION 19
 TOMPKINS TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2022473
 Liber 1533 Page 353
 Page 1 of 1
 Jackson Co., MI
 Recorded
 12/12/96 01:05P
 Jerry McDevitt
 Register of Deeds

For corners in

JACKSON
 (County)

Located In: Corner Code #

- | | | | | | | | |
|------------------------------------|---|----------|---|---|----------|---|-----|
| 1. Public Land Survey | T | <u>1</u> | S | R | <u>2</u> | W | B-8 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | R | | | |
| | S | | T | R | | | |
| 3. Miscellaneous Property in Sec. | S | | T | R | | | |
| | S | | T | R | | | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DEAN R GUTEKUNST, in a field survey on July 18, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post not set in original survey.
 Not recorded in P. A. - 74



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Established center of Section 19 at intersection of North & South and East & West $\frac{1}{4}$ lines.
 No corner was found.
 Set a Standard Jackson County Monument for Center of Section, to surface of ground.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-8 T1S, R2W Corner is a 4" diameter X 30" concrete monument with a $\frac{1}{2}$ " X 30" steel rod and an aluminum cap stamped LS 18658, which is the standard monument for Jackson County.

- | | | | |
|---------|---|--------|------------------------------|
| N 30° E | 15" Hickory | 88.79' | 40d & washer on West side |
| N 80° E | 14" Hickory | 69.38' | 40d & washer on South side |
| S 40° E | 19" Walnut | 74.57' | 40d & washer on South side |
| S-30° W | 7" Oak | 26.50' | 40d & washer on East side |
| N 40° W | Double (12" & 22") Hickory | 6.69' | 40d & washer on East side |
| N 15° W | 27" Oak | 24.09' | 40d & washer on East side |
| East | Capped iron on center line of Townley Road (gravel) | | 15.14' (capped iron # 18658) |
| West | Steel post and survey marker sign attached | | 3.0' |

Signed by Dean R. Gutekunst Date November 30, 1996
 Surveyor's Michigan License No. 18658