

JACKSON COUNTY APPROVED LAND CORNER P.A. 345 of 1990

Chairman [Signature] Date Dec 10, 1997

SOUTH 1/4 CORNER SECTION 32 TOMPKINS TOWNSHIP LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

#2057141 Liber 1558 Page 536 Page 1 of 1 Jackson Co., MI Recorded 12/29/1997 10:27A Mindy Reilly Register of Deeds

For corners in

JACKSON COUNTY (County) TOMPKINS TOWNSHIP 1. Public Land Survey Located In: T1S R2W Corner Code # D-13 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R

SURVEY & REMONUMENTATION

SEP 5 1998

Register of Deeds Stamp & File Number

SECTION

4. Lot No. Recorded Plat 5. Private Claims

I, DAVID L. CLIFFORD, in a field survey on DECEMBER 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell 11,32 contains a circled 'O'.

- A. Description of original monument and accessories and/or subsequent restoration: 1. JOSEPH WAMPLER DS SET POST IN JANUARY 1824; W.O. 9 N84W 40; LIN 5 N31E 13 2. JOHN HOLCROFT REPORTED IN MAY 1880 FOUND STAKE AT CORNER AND REMAINS OF 1ST WITNESS ALSO WITNESSES BY H.F. BEAN; BURR OAK 6 S77 1/4 W 126 1/2; SWP. OAK 24 N60 1/4 W 137. 3. H.F. BEAN REPORTED POST BROKE OFF & LIME 4' NORTH OF CEN. OF DITCH WEST; MAPLE 7 N87W 92 ; SWP OAK 28 N60W 136 4. RON HELSEL, RLS 18994, USED CORNER IN AN UNRECORDED ACT 132 IN OCTOBER 1994 AS A FOUND 1/2" IRON WITH NO MENTION OF WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 1/2" BAR 1' EAST OF A NORTH-SOUTH ROW FENCE FOR WELLMAN ROAD AND 1' NORTH OF AN OLD ANCHOR POST. EXCAVATED 4' X 4' HOLE AROUND ANCHOR POST AND ANOTHER 4' X 4' HOLE CENTERED ON 1/2 WAY AND ON LINE POSITION BETWEEN SECTION CORNERS. BOTH OF THESE POSITIONS ARE 4' NORTH OF AN EAST-WEST DITCH. DID NOT FIND ANY EVIDENCE OF AN HISTORICAL NATURE. RETURNED WITH ROAD COMMISSION BACKHOE ON MAY 12 1997 AND EXCAVATED 6' X 20' HOLE IMMEDIATELY NORTH OF EAST-WEST DITCH. DID NOT FIND ANY EVIDENCE OF CORNER. DID NOT ACCEPT 1/2" BAR BECAUSE IT IS HALF WAY AND ON BETWEEN A FIRECLAY AT C-13 AND A FALSE CORNER AT E-11. CONSIDERED CORNER LOST AND SET 36" X 3/4" ALUMINUM PIPE MONUMENT WITH 3" ALUMINUM CAP HALF WAY AND ON LINE BETWEEN C-11 & E-11 WHICH ARE BOTH STANDARD MONUMENTS WHICH HAVE BEEN ACCEPTED UNDER PA 345. MONUMENT LIES 4' NORTH OF EAST-WEST DITCH WHICH AGREES WITH BEANS INFORMATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 3/4" X 36" ALUMINUM PIPE MONUMENT WITH 3" ALUMINUM CAP STAMPED LS 25837 SET NAIL & TAG #25837 NORTH SIDE 10" ELM, 108° NAZ, 20.17' SET NAIL & TAG #25837 WEST SIDE 18" ASH, 189° NAZ, 230.47' SET NAIL & TAG #25837 NORTH SIDE 8" ELM, 267° NAZ, 184.74' SET NAIL & TAG #25837 EAST SIDE 15" ELM, 348° NAZ, 193.20 NW CORNER FOUNDATION HOUSE #7999, 171° NAZ, 192.38 SURVEY MARKER SIGN POST 90° NAZ, 1.0'

Signed by David L. Clifford Date DECEMBER 9, 1997 Surveyor's Michigan License No. 25837