

Chairman David Clifford  
Date Nov. 18, 1998

**NORTHWEST CORNER SECTION 9  
TOMPKINS TOWNSHIP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

JACKSON Located in: \_\_\_\_\_  
(County)

Corner Code 4



2099037  
Page: 1 of 1  
12/21/1998 10:57A  
L-1589 P-261

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | T <u>1S</u> R <u>2W</u> | <u>E-3</u> |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID L. CLIFFORD, in a field survey on JULY 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3					●								
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL POST SET BY LUCIUS LYON D.S. IN FEB. 1825: B.O., 17", S52W, 32; W.O., 13", N49E, 112
- IN MAY 1886 JOHN HOLCROFT REPORTED: "FOUND LONG PEAKED STONE AT CORNER- WITNESSES BOTH GONE; CORNER HAS BEEN KEPT UP; W.O. 14", N15 1/2 W, 59 1/2 W. ASH 6", N78E, 56 (37.0)
- JACKSON COUNTY ROAD COMMISSION WITNESSES IDENTIFY CORNER AS A SET 1/2" REINFORCING ROD OVER A FIRE CLAY POST 2' DEEP: ASH, 18" N80°E, 37.10'; TW. CHERRY, 8" S20°W, 63.00'; ELM 8", N28°W, 54.70'; R. OAK 12", N65°E, 37.10'; HICK, 8", S78°E, 29.90'
- RON LESTER LS #18998 RECORDED CORNER IN LIBER 2 PAGE 273 IN AUGUST 1973 AS A FOUND 1/2" BAR IN MONUMENT BOX: NAIL & TAG #18998 SOUTH SIDE 30" OAK, NE, 36.96'; NAIL & TAG #18998 NORTH SIDE 15" HICKORY, EAST, 29.89'; NAIL & TAG #18998 NORTH SIDE 6" OAK, SW, 86.84'
- DON BISSELL LS#10655 RECORDED CORNER IN LIBER 4 PAGE 74 IN JAN. 1990 AS A FOUND 1/2" PIPE IN A MONUMENT BOX: EAST - 6.2' - CENTERLINE ROAD; N38°E - 60.17' - 10" OAK; N59°E - 31.67' - 10" OAK; S68°E - 30.00' - 8" OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" PIPE IN MONUMENT BOX MATCHING HOLCROFT'S ASH WITNESS TO NORTHEAST; ASH, OAK AND HICKORY WITNESSES OF ROAD COMMISSION; LESTER'S 30" OAK AND 15" HICKORY WITNESSES AND ALL OF BISSELL'S WITNESSES (2 OAK WITNESSES ARE ACTUALLY HICKORIES). EXCAVATED MONUMENT BOX AND FOUND FIRE CLAY SURROUNDED BY BRICK 2' DEEP. ACCEPTED FIRECLAY AS CORNER AS PERPETUATED BY HOLCROFT AND SET 4" X 20" CAST IRON HARRISON MONUMENT ABOVE IT. MEASURED SOUTH 2669.30 TO E-4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-3 T1S R2W  
4" X 20" CAST IRON HARRISON MONUMENT AND BRASS CAP STAMPED 25837 6.2' WEST OF CENTERLINE ONONDAGA ROAD  
NAIL & PLAIN WHITE TAG IN SE SIDE 26" OAK, N35°E, 60.15'  
NAIL & PLAIN WHITE TAG IN NORTH SIDE 15" HICKORY, N70°E, 31.68'  
NAIL & PLAIN WHITE TAG IN SOUTH SIDE 28" OAK, N60°E, 37.00'  
NAIL & PLAIN WHITE TAG IN NORTH SIDE 15" HICKORY, S65°E, 30.78'  
NAIL & PLAIN WHITE TAG IN SOUTH SIDE 30" ASH, N85°E, 37.19'  
1/2" BAR & CAP #20707, EAST, 33.00'  
SURVEY MARKER SIGN POST, EAST, 33.00'

Signed by David Clifford Date NOVEMBER 17, 1998

Surveyor's Michigan License No. 25837

