

Chairman Dean C. Gutierrez

Date May 15, 1997

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

#2037794  
 Liber 1544 Page 363  
 Page 1 of 2  
 Jackson Co., MI  
 Recorded  
 06/11/97 11:01A  
 Mindy Reilly  
 Register of Deeds

For corners in

JACKSON  
 (County)

Located In:

Corner Code #

- |                                    |  |       |
|------------------------------------|--|-------|
| 1. Public Land Survey              | T <u>1S</u> R <u>2W</u>                | H-5   |
|                                    | T <u>   </u> R <u>   </u>              | _____ |
|                                    | T <u>   </u> R <u>   </u>              | _____ |
|                                    | T <u>   </u> R <u>   </u>              | _____ |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |

SURVEY &  
 REMONUMENTATION

APR 28 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DAVID CLIFFORD, in a field survey on APRIL 10, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- POST SET IN ORIGINAL GOVERNMENT SURVEY BY LUCIUS LYON, D.S. IN FEBRUARY, 1825 AND TWO WITNESSES RECORDED:  
 B.O. 18 S41E 39 (25.7')  
 W.O. 13 N34E 87 (57.4')
- IN NOVEMBER 1885 JOHN HOLCROFT FOUND STAKE AT CORNER SET BY WM. CROUL WHEN HE WAS COUNTY SURVEYOR AND ALSO WHERE HE FOUND REMAINS OF BOTH WITNESSES. HE SET A FIRE CLAY AND RECORDED 2 WITNESSES:  
 W. OAK 12 S13-3/4E 41 $\frac{1}{2}$ ' (27.4')  
 MAPLE 13 N $\frac{1}{2}$ E 158-3/4 (104.8')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER ON APRIL 3, 1997 AND FOUND  $\frac{1}{2}$ " PIPE IN MONUMENT BOX MATCHING ALL 3 JCRC WITNESSES. NONE OF HOLCROFT'S WITNESSES STILL STAND. EXCAVATED THROUGH BOTTOM OF MONUMENT BOX AND HIT STONE AT DEPTH OF 18". RETURNED TO SITE APRIL 10 AND EXCAVATED 2' DIAMETER HOLE AND REMOVED MONUMENT BOX AND STONE AND FOUND COMPLETE FIRE CLAY IN GOOD CONDITION BELOW STONE AND PIPE. ACCEPTED FIRE CLAY AS PERPETUATION OF CORNER REPLACED FIRE CLAY WITH 4" DIAMETER CAST IRON MONUMENT AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-5 T1S R2W  
 4 INCH DIAMETER BY 30" LONG CAST IRON HARRISON MONUMENT AND CAP STAMPED LS 25837
- |          |             |         |                                 |
|----------|-------------|---------|---------------------------------|
| 004° NAZ | 22" OAK     | 22.82'  | NAIL & TAG #28409 IN WEST SIDE  |
| 047° NAZ | 18" MAPLE   | 25.03'  | NAIL & TAG #28409 IN SE SIDE    |
| 137° NAZ | 18" HICKORY | 40.07'  | NAIL & TAG #28409 IN SE SIDE    |
| 186° NAZ |             | 26.67'  | SURVEY MARKER SIGN POST         |
| 254° NAZ | 36" OAK     | 107.10' | NAIL & TAG #28409 IN NORTH SIDE |
| 313° NAZ | 36" OAK     | 36.75'  | NAIL & TAG #28409 IN NE SIDE    |

NOTE: NAZ IS MAGNETIC AZIMUTH MEASURED FROM NORTH.

Signed by David Clifford  
 Surveyor's Michigan License No. 25837

Date APRIL 26, 1997



Record 255