

**JACKSON COUNTY  
APPROVED LAND CORNER  
P.A. 345 of 1999**

Chairman *Dean R. Galt*  
Dec 26, 1996

CENTER SECTION 34  
TOMPKINS TOWNSHIP

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

#2023680  
Liber 1534 Page 200  
Page 1 of 1  
Jackson Co., MI  
Recorded  
12/27/96 12:06P  
Jerry McDevitt  
Register of Deeds

For corners in  
JACKSON  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	1S	R	2W	H-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, RONALD L. ENGER, in a field survey on DECEMBER 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1. POST NOT SET IN ORIGINAL GOVERNMENT SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND NO EVIDENCE THAT CORNER HAD EVER BEEN SET. TRAVERSED SECTION 34 AND SET STANDARD MONUMENT AT INTERSECTION OF 1/4 LINES. MONUMENT FALLS 15' NORTH OF CENTERLINE LINCOLN ROAD, 2' EAST OF CENTERLINE ABBEY ROAD AND 2' EAST OF FENCE TO SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-12 T1S R2W  
4 INCH DIAMETER BY 36" LONG CONCRETE MONUMENT WITH ALUMINUM CAP STAMPED LS 28409  
082° NAZ 42" MAPLE 185.51' NAIL & TAG IN SOUTH SIDE  
118° NAZ 29" MAPLE 99.50' NAIL & TAG IN NE SIDE  
182° NAZ 45.87' SURVEY MARKER SIGN POST  
262° NAZ 26" OAK 322.31' NAIL & TAG IN NORTH SIDE  
323° NAZ POWER POLE 112.91' NAIL & TAG IN NE SIDE  
NOTE: NAIL & TAGS ARE 20D SPIKES AND YELLOW PLASTIC TAGS STAMPED PS 25837  
NOTE: NAZ IS MAGNETIC AZIMUTH MEASURED FROM NORTH.

12-20

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by *R. Enger* Date DECEMBER 21, 1996  
Surveyor's Michigan License No. 28409