

<sup>24-45</sup>  
**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 343 of 1990**

Chairman *Donald L. Enger*

Date Nov. 29, 1995

SOUTH 1/4 CORNER SECTION 34  
 TOMPKINS TOWNSHIP

LIBER 1501 PAGE 1092

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

JACKSON

(County)

Located In:

Corner Code #

1. Public Land Survey

T 1S R 2W H-13

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
 in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_



STATE OF MICHIGAN  
 JACKSON COUNTY  
 RECORDED

29 DEC 95 10:28 A.M.

GERALD J. McDEVITT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RONALD L. ENGER, in a field survey on NOVEMBER 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1. **POST SET IN ORIGINAL GOVERNMENT SURVEY BY JOSEPH WAMPLER, DEPUTY SURVEYOR, IN JANUARY 1824 AND TWO WITNESSES RECORDED:**

W.O. 30 N30E 72  
 B.O. 30 N40W 443

2. ON OCTOBER 31, 1885, JOHN HOLCROFT REPORTED: "FOUND OLD STAKE AND REMAINS OF 1ST WITNESS" AND RECORDED TWO WITNESSES:

W. OAK 12 EAST 156-1/4 (103.13')  
 MAPLE 5 N37-1/2W 53 (34.98')

\$ 2.00 REMONUMENTATION  
 \$ 7.00 CORNER REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND FIRECLAY POST WITH BRICK AND 3/4" IRON PIPE WITH CAP REG #7863 ON LINE WITH FENCE TO NORTH. NO VISIBLE SIGN OF GLO OR HOLCROFT WITNESSES. ACCEPTED FIRE CLAY AS A PERPETUATION OF THE ORIGINAL CORNER AND REPLACED IT WITH STANDARD MONUMENT FOR PA 345 REMONUMENTATION IN JACKSON COUNTY. PLACED IRON PIPE ON NORTHWEST SIDE OF CORNER. COULD NOT RESET FIRECLAY ON ANY SIDE DUE TO HUGE ROCKS IN THE WAY.

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 H-13 T1S R2W

4 INCH DIAMETER BY 36" LONG CONCRETE MONUMENT WITH ALUMINUM CAP STAMPED LS 28409

10° NAZ	8" POPLAR	7.63	NAIL AND TAG LS #28409 IN EAST SIDE
111° NAZ	10" POPLAR	23.44	NAIL AND TAG LS #28409 IN SOUTHWEST SIDE
124° NAZ	12" POPLAR	18.45	NAIL AND TAG LS #28409 IN NORTHEAST SIDE
270° NAZ	10" POPLAR	37.50	NAIL AND TAG LS #28409 IN SOUTH SIDE
285° NAZ	6" POPLAR	4.52	NAIL AND TAG LS #28409 IN SOUTH SIDE

MONUMENT IS APPROXIMATELY 1' ABOVE GROUND ON FENCE TO NORTH AND 0.8' SOUTH OF EAST-WEST FENCE. NOTE: NAZ IS MAGNETIC AZIMUTH MEASURED FROM NORTH

Signed by *Ronald L. Enger*

Date NOVEMBER 20, 1995

Surveyor's Michigan License No. 28409