

**JACKSON COUNTY  
APPROVED LAND CORNER  
P.A. 347 of 1990**

**NE CORNER SECTION 14  
TOMPKINS TOWNSHIP**

Chairman *Don R. Galdames*  
Date MAY 15, 1997

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

#2037791  
Liber 1544 Page 360  
Page 1 of 1  
Jackson Co., MI  
Recorded  
06/11/97 10:58A  
Mindy Reilly  
Register of Deeds

For corners in

<u>JACKSON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>1S</u> R <u>2W</u>	<u>J-5</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

**SURVEY &  
REMONUMENTATION**

**APR 07 1998**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

DAVID CLIFFORD in a field survey on APRIL 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5										⊙			
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY LUCIUS LYON, D.S. IN FEBRUARY, 1825 AND TWO WITNESSES RECORDED:  
W.O. 16 N44W 34 (22.4')  
W.O. 18 S66E 161 (106.3')

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER ON APRIL 3, 1997 AND FOUND 1/2" BAR IN MONUMENT BOX WITH ALL OF MY 1988 WITNESSES STILL STANDING. NONE OF HOLCROFT'S WITNESSES STILL STAND. EXCAVATED THROUGH BOTTOM OF MONUMENT BOX AND HIT STONE AT DEPTH OF 12". RETURNED TO SITE APRIL 10 AND EXCAVATED 2' DIAMETER HOLE AND REMOVED MONUMENT BOX AND STONE AND FOUND COMPLETE FIRE CLAY IN GOOD CONDITION BELOW STONE AND PIPE. ACCEPTED FIRE CLAY AS PERPETUATION OF CORNER. REPLACED FIRE CLAY WITH 4" DIAMETER CAST IRON MONUMENT AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-5 T1S R2W  
4 INCH DIAMETER BY 30" LONG CAST IRON HARRISON MONUMENT AND CAP STAMPED LS 25837
- |          |                     |                                 |
|----------|---------------------|---------------------------------|
| 85° NAZ  | 26.67'              | SURVEY MARKER SIGN POST         |
| 85° NAZ  | 6" SQUARE WOOD POST | NAIL & TAG #25837 IN TOP        |
| 241° NAZ | 12" WALNUT          | NAIL & TAG #28409 IN NORTH SIDE |
| 249° NAZ | 12" WALNUT          | NAIL & TAG #28409 IN NORTH SIDE |
| 256° NAZ | 14" WALNUT          | NAIL & TAG #28409 IN NORTH SIDE |
| 263° NAZ | 15" WALNUT          | NAIL & TAG #28409 IN NORTH SIDE |

NOTE: NAZ IS MAGNETIC AZIMUTH MEASURED FROM NORTH.

Signed by *David Clifford*  
Surveyor's Michigan License No. 25837

Date APRIL 26, 1997

