

Chairman Dean K. Hubbard
 Date Nov 18, 1998

NORTHWEST CORNER SECTION 1
 TOMPKINS TOWNSHIP
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

JACKSON Located In: Corner Code #
 (County)

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>1S</u> R <u>2W</u> | <u>K-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |



2099036
 Page: 1 of 1
 12/21/1998 10:57A
 L-1589 P-280

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on NOVEMBER 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL POST SET BY LUCIUS LYON D.S. IN FEB. 1825 84 LKS (55.4') WEST OF THE STANDARD CORNER: R.O., 19', S9E, 33; HICKORY, 20", S46 1/2 W, 60
- IN MAY 1886 JOHN HOLCROFT REPORTED: "FOUND POINT OF OLD STAKE AND REMAINS OF BOTH WITNESSES: W. OAK, 12", S49W, 32; ELM, 30", S49W, 215
- CONSUMERS POWER COMPANY IDENTIFIED CORNER AS A SET "T" IRON ON FENCE LINE TO SOUTH IN MAY 1967. N35°W, 20" HICKORY, 30.14'; S10°E, 14" HICKORY, 24.63'; S60°E, 33" OAK, 59.59'
- DEAN GUTEKUNST LS #18658 IDENTIFIED CORNER IN A SURVEY IN MARCH 1971 AS A CONSUMERS POWER COMPANY "T" IRON.
- RON LESTER LS #18998 RECORDED CORNER IN LIBER 4 PAGE 176 OF CORNERS IN MARCH 1981 AS A 4" X 36" CONCRETE MONUMENT WITH A 1/2" X 38" REBAR & CAP # 18998 IN PLACE OF A FIRECLAY FOUND BY EXCAVATION: NAIL & TAG #18998 EAST SIDE 10" HICKORY, NNW, 29.36'; NAIL & TAG #18998 SOUTH SIDE 6" CHERRY, NE, 40.44'; NAIL & TAG #18998 NW SIDE 24" OAK, SSE, 26.71'; NAIL & TAG #18998 WEST SIDE 6" HICKORY, SW, 32.52'; CONCRETE MONUMENT WITH CAP #18998, K-13 ONONDAGA TWP., EAST, 54.68'; CONCRETE MONUMENT WITH CAP #18998, PROPERTY CONTROLLING CORNER, EAST, 104.18'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 4" CONCRETE MONUMENT WITH 1/2" REBAR MATCHING ALL OF LESTER'S WITNESSES. TRAVERSED NORTH LINE OF SECTION 2 AND SET CAST IRON HARRISON MONUMENT 0.17' NORTH OF CONCRETE MONUMENT ON THE BASE LINE. REMOVED CONCRETE MONUMENT IN ORDER TO PLACE HARRISON. MEASURED WEST 2657.75' TO J-1. MEASURED SOUTH 2433.60' TO K-2. MEASURED EAST 2655.08' TO L-1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 T1S R2W
 4" X 30" CAST IRON HARRISON MONUMENT AND BRASS CAP STAMPED 25837 1' NORTH OF CENTERLINE BASELINE ROAD
 NAIL & TAG 18998 IN SE SIDE 19" HICKORY, N78°E, 80.99'
 NAIL & TAG 25837 IN NORTH SIDE 39" OAK, S63°E, 60.45'
 NAIL & TAG 25837 IN EAST SIDE 17" HICKORY, S10°E, 25.89'
 NAIL & TAG 18998 IN NW SIDE 15" HICKORY, S60°W, 32.55'
 NAIL & TAG 18998 IN WEST SIDE 31" HICKORY, N23°W, 29.31'
 CONCRETE MONUMENT (K-13, T1N, R2W), S88°E, 54.68'
 CONCRETE MONUMENT (PROPERTY CONTROLLING CORNER), S88°E, 104.20'
 "T" IRON, S35°E, 1.3'
 SURVEY MARKER SIGN POST, S04°W, 36.50'

Signed by David L. Clifford Date NOVEMBER 17, 1998

Surveyor's Michigan License No. 25837

