

JACKSON COUNTY
 APPROVED LAND CORNER
 P.A. 345 of 1990

Chairman Dean Hubbard
 Date Dec. 9, 1998

WEST 1/4 CORNER SECTION 1
 TOMPKINS TOWNSHIP
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

JACKSON Located In: _____ Corner Code # _____
 (County)

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>1S</u> R <u>R2W</u> | <u>K-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |



2099034
 Page: 1 of 1
 12/21/1998 10:57A
 L-1589 P-278

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2	1		
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, DAVID L. CLIFFORD, in a field survey on OCTOBER 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL POST SET BY LUCIUS LYON D.S. IN FEB. 1825: W.O., 22", N89E, 9; W.O., 22", N70W, 92
- IN NOVEMBER 1885 JOHN HOLCROFT REPORTED: "FOUND 1ST WITNESS STUMP AND REMAINS OF 2ND WITNESS: DBL B.O. 18", N48E, 7; HICK. 10", S7E, 29 1/2"
- CONSUMERS POWER COMPANY SURVEY OF THEIR FEE STRIP IN SECTION 1 SHOWS A MONUMENT AT K-2 BUT DOES NOT DESCRIBE IT OR GIVE WITNESSES.
- THIS SURVEYOR TRAVERSED TO CORNER IN OCTOBER 1988 WHILE WORKING ON THE SUPER CONDUCTOR SUPER COLLIDER SURVEY. I FOUND A "T" IRON WITH CONSUMERS CAP ON THE EAST SIDE OF A RAILROAD TIE ANCHOR POST AND TOOK 4 WITNESSES: NAIL & TAG IN RAILROAD TIE FENCE POST, N2°E, 19.10'; NAIL & TAG IN RAILROAD TIE FENCE POST, S85°E, 25.50'; SW LEG TRANSMISSION TOWER, N48°E, 182.80'; EAST CORNER POLE BARN, S25°W, 219.20'
- MARK FAUSER IN THE EMPLOY OF HIS FATHER, GLENN FAUSER RLS # 18657, OBTAINED MY 1988 INFORMATION FROM MY FILES IN JULY 1997 AND UPON LEARNING THAT I PLANNED TO EXCAVATE CORNER EXCAVATED AROUND IRON AND REPORTED TO ME THAT HE HAD FOUND A BROKEN FIRECLAY AND NUMEROUS PIECES OF BROKEN BRICK MIXED IN WITH STONES AROUND RAILROAD RAIL FENCE POST. HE SET A 1/2" BAR & CAP IN PLACE OF THE "T" IRON.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR & CAP #18657 AT THE REMAINS OF A OLD FENCE CORNER MATCHING 2 OF MY 1988 WITNESSES. ACCEPTED BAR & CAP AS PERPETUATION OF CORNER BASED ON MARK FAUSER'S REPORT OF EVIDENCE FOUND IN EXCAVATION. WHILE EXCAVATING TO SET MONUMENT FOUND 2 PIECES OF BROKEN FIRECLAY, SEVERAL PIECES OF BROKEN BRICK AND A DEPOSIT OF LIME 30" DEEP AROUND IRON. SET STANDARD CONCRETE MONUMENT 18" DEEP. AS THIS IS NOW OPEN FIELDS DID NOT SET SIGN & POST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-2 T1S R2W
 4" X 36" CONCRETE MONUMENT WITH ALUMINUM CAP STAMPED 25837
 NAIL & TAG #28409 IN EAST ROOT 16" HICKORY, N3°E, 234.82'
 NAIL & TAG #28409 IN EAST ROOT 12" HICKORY, N11°E, 227.25'
 NAIL & TAG #28409 IN EAST ROOT 7" HICKORY, N25°E, 242.06'
 SW CORNER SW LEG TRANSMISSION TOWER, N48°E, 182.63'
 NW CORNER POLE BARN, S24°W, 219.42'



Signed by David L. Clifford

Date NOVEMBER 17, 1998

Surveyor's Michigan License No. 25837