

**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 345 of 1990**

Chairman Don R. [Signature]  
 Date MAY 15, 1997

W $\frac{1}{2}$  SECTION 24  
 TOMPKINS TOWNSHIP  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

#2037795  
 Liber 1544 Page 364  
 Page 1 of 2  
 Jackson Co., MI  
 Recorded  
 06/11/97 11:02A  
 Mindy Reilly  
 Register of Deeds

For corners in

JACKSON (County)	Located In:	Corner Code #
1. Public Land Survey	T1S R 2W	K-8
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**SURVEY &  
 REMONUMENTATION**  
 APR 07 1998  
 SECTION  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

DAVID L. CLIFFORD, in a field survey on APRIL 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY LUCIUS LYON, D.S. IN FEBRUARY 1825 AND TWO WITNESSES RECORDED:  
 W.OAK 24 N57W 42 (27.72')  
 W.OAK 15 N40 $\frac{1}{2}$ E 33 (21.78')

CONTINUED ON BACK



3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER IN DECEMBER 1996 AND FOUND A 5/8' IRON IN MONUMENT BOX. EXCAVATED BOTTOM OF BOX AND FOUND LARGE STONE UNDER IRON. RETURNED ON APRIL 10, 1997 AND REMOVED BOX AND DUG 3' DIAMETER HOLE 2' DEEP AND FOUND LARGE POINTED STONE. FOUND PIECES OF IRON AND BRICK ON NORTH SIDE OF STONE AND BOTTOM 12" OF FIRE CLAY UNDER BRICK AND IRON. BELIEVE LONG POINTED STONE IS STONE MENTIONED BY HOLCROFT AND ACCEPTED FIRE CLAY AS PERPETUATION OF CORNER AND REPLACED WITH CAST IRON MONUMENT. LEFT FIRE CLAY IN HOLE ON SOUTH SIDE OF MONUMENT AND RESET MONUMENT BOX.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 T1S R2W  
 4 INCH DIAMETER BY 30" LONG CAST IRON HARRISON MONUMENT AND CAP STAMPED LS 25837  
 4° NAZ SURVEY MARKER SIGN POST 25.55'  
 87° NAZ 33" OAK 198.55' NAIL & TAG #28409 IN SOUTH SIDE  
 170° NAZ CORNER FENCE POST 28.46' NAIL & TAG #28409 IN WEST SIDE  
 200° NAZ NE CORNER HOUSE FOUNDATION 73.83' CORNER STONE FOUNDATION #6283  
 230° NAZ 36" MAPLE 58.76' NAIL & TAG #28409 IN NORTH SIDE  
 285° NAZ 48" OAK 267.73 NAIL & TAG #24809 IN NORTH SIDE  
 CENTER LINE MAPLE LANE SOUTH 2' FOUND IRON SOUTH 0.4'(NOT RESET)

NOTE: NAZ IS MAGNETIC AZIMUTH MEASURED FROM NORTH.

Signed by David Clifford Date MAY 8, 1997  
 Surveyor's Michigan License No. 25837