

Chairman Dean K. Hallett  
 Date Dec. 30, 1994

CENTER SECTION 25  
 TOMPKINS TOWNSHIP  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

JACKSON  
 (County)

Located In:

Corner Code ≠

- |                                       |   |           |   |           |             |
|---------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey                 | T | <u>1S</u> | R | <u>2W</u> | <u>L-10</u> |
|                                       | T | _____     | R | _____     | _____       |
|                                       | T | _____     | R | _____     | _____       |
|                                       | T | _____     | R | _____     | _____       |
| Property Controlling in Section       | S | _____     | T | _____     | _____       |
| 3. Miscellaneous Property in Sec      | S | _____     | T | _____     | _____       |
|                                       | S | _____     | T | _____     | _____       |
| 4. Lot No. _____, Recorded Plat _____ | S | _____     | T | _____     | _____       |
| 5. Private Claims _____               | S | _____     | T | _____     | _____       |

STATE OF MICHIGAN  
 JACKSON COUNTY  
 RECORDED

2 MAY 95 8:24 A.M.

GERALD J. McDEVITT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**SURVEY & REMONUMENTATION**

APR 17 1995

**COMMISSION**

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, RONALD L. ENGER in a field survey on OCTOBER 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


A. Description of original monument and accessories and/or subsequent restoration:

1. INFORMATION IN THE FILES OF THE JACKSON COUNTY ROAD COMMISSION DATED 3/18/67 DESCRIBES THE CORNER MARKER AS AN IRON POST "ON NORTH-SOUTH LINE EAST-WEST LINE" AND SHOWS 6 WITNESSES: N-14-E 18" OAK 121.55; S-84-E 18" HICKORY 51.55; S-50-E 20" MULBERRY 45.00; S-21-W 20" OAK 52.65 AND N-33-W 6" HICKORY 36.40 AND NOTES "IN LINE WITH FENCE EAST" AND "MON BOX SET 1974".  
 CONTINUED ON BACK

\$ 2.00 REMONUMENTATION  
 \$ 9.00 CORNER REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2 REROD IN MONUMENT BOX 2' WEST OF CENTERLINE DIXON ROAD ON FENCE LINE TO EAST AND WEST. EXCAVATED BOTTOM OF BOX AND FOUND REBAR WAS INSIDE OF 3/4" PIPE. PULLED PIPE AND BAR AND EXCAVATED FURTHER AND FOUND ANOTHER 1/2" BAR IN A 3/4" PIPE UNDER FIRST MENTIONED. FOUND STACK OF NESTED MARKERS ARE 3.50' SOUTH AND 0.05' EAST OF OUR CALCULATION OF THE INTERSECTION OF THE 1/4 LINES. ROAD COMMISSION HICKORY IN SE QUADRANT AND MULBERRY WITNESSES EXIST, BUT WE NOTE A DISCREPANCY IN THE DISTANCE TO THE MULBERRY. ACCEPTED PIPES AND BARS AS CORNER AND SET JACKSON COUNTY REMONUMENTATION MONUMENT AND CAP IN MONUMENT BOX IN THEIR PLACE.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-10 T1S R2W  
 JACKSON COUNTY REMONUMENTATION MONUMENT AND CAP IN MONUMENT BOX.  
 050° NAZ, 8" MAPLE 50.75 NAIL AND TAG LS #28409 IN NW SIDE  
 102° NAZ, 20" HICKORY 51.57 NAIL AND TAG LS #28409 IN S SIDE(JCRC WIT)  
 132° NAZ, 30" MULBERRY 42.65 NAIL AND TAG LS #28409 IN N SIDE(JCRC HAD 45.00)  
 269° NAZ, 18" TWIN OAK 81.37 NAIL AND TAG LS #28409 IN N SIDE  
 325° NAZ, HOUSE 156.00 SW CORNER

NOTE: NAZ IS MAGNETIC ALMUTH MEASURED FROM NORTH

Signed by Ronald L Enger

Date DECEMBER 30, 1994

Surveyor's Michigan License No. 28409

L-10 T1S R2W  
PART A CONTINUED

2. A SURVEY BY TIM VANGIESON, LS 24621, DATED DECEMBER 20, 1990, IDENTIFIES THE CORNER AS A  $\frac{1}{2}$ " ROD, SHOWS S 89°08'29"E ON THE  $\frac{1}{4}$  LINE IN EAST  $\frac{1}{2}$  OF THE SECTION AND S 88°59'44"E ON THE  $\frac{1}{4}$  LINE IN WEST  $\frac{1}{2}$  OF THE SECTION, AND SHOWS 4 WITNESSES: 60D IN 16" OAK S 81°E 51.50', 60D IN 30" BOX ELDER S 45°E 44.51', 60D IN TWIN 18" OAK S 86°W 32.09', 60D IN 10" ELM N 55°W 42.75'