

REQUIREMENT OF ACT 74, MICH. P.A. 1970

W. Post Section 34 Leoni Twp.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 2 N. S., R. 1 E.	G-12
2. PROPERTY CONTROLLING IN SECTION	T. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

2-205

REGISTER OF DEEDS STAMP AND FILING NUMBER

Richard E. Gutekunst, RLS do hereby certify that under requirements of P.A. 74, Michigan, P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on December 9 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- W. Oak 7" S16 W 245 links
 - B. Oak 2 1/4" N48 1/2 E 238 links
 - Tamarack 8" N3 E 52 links
 - Tamarack 7" N38 W 36 links
 - Maple 2" S75 W 8.65 links
 - Y. Oak 8" S73 E 41.4 links
 - Y. Oak 7" N45 E 43.7 links
 - Elm 10" N40 W 46.5 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found fireclay. Set capped iron on N. Side, set metal post.

Found iron 5.5' WNW. (3/4 X 5/8) Post about 1/4 South of E. & W. Ditch & Approx. 10' W of point where Ditch turns North

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- West 9" Oak 70.68'
 - N45 W 6" Maple 18.82'
 - S20 E DBL. Maple 38.04'

SIGNED BY Richard E. Gutekunst DATE June 6, 1973

SURVEYOR'S MICHIGAN REGISTRATION NO. 7863

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____