

Chairman Dean R. Hultham
 Date April 9, 1997

Center of Section 36, Leoni Township
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2031969
 Liber 1540 Page 150
 Page 1 of 1
 Jackson Co., MI
 Recorded
 04/10/97 08:27A
 Mindy Reilly
 Register of Deeds

For corners in
JACKSON
 (County)

Located in:

Corner Code #

SURVEY &
 REMONUMENTATION

- | | | |
|---------------------------------------|----------------|-------|
| 1. Public Land Survey | T2S R1E | L-12 |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| 2. Property Controlling in Section | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	●							
13													

I, David E. Erickson, in a field survey on March 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not established in original government survey of 1825, nor subsequently by H.F. Bean around 1888. No other record of this corner being established in the field.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched area at intersection of quarter lines. Point falls 20'± North of an East-West fence line, at the West edge of a brushy marsh. No occupation North and South. Established the corner at the intersection of quarter lines. Set a 60" Aluminum pipe with cap to monument this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set a 60" aluminum pipe with cap stamped "L-12, T2S-R1E, 1997, LS #29245".

- | | | |
|-----------|--|----------|
| N 37° E | Set nail & tag #29245, West side 5" Oak | 58.83' |
| N 65° E | Set nail & tag #29245, Southeast side 8" Oak | 29.23' |
| S 65° W | Set nail & tag #29245, South side 11" Oak | 77.46' |
| N 72° W | Set nail & tag #29245, North side 15" Oak | 62.80' |
| North | County Surveyor sign post | 1.0' |
| Northerly | Corner "L-11" as remonumented | 2648.84' |
| Easterly | Corner "M-12" as remonumented | 2655.13' |
| Southerly | Corner "L-13" as remonumented | 2653.53' |
| Westerly | Corner "K-12" as remonumented | 2651.16' |

NOTE: Bearings are magnetic



Signed by David E. Erickson Date 4-8-97
 Surveyor's Michigan License No. 29245

Record 295