

ACTING  
 (Signature)  
 TIMOTHY G. VAN SICKLESON  
 Date MARCH 12, 1997

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

#2029636  
 Liber 1538 Page 532  
 Page 1 of 1  
 Jackson Co., MI  
 Recorded  
 03/13/97 03:38P  
 Mindy Reilly  
 Register of Deeds

For corners in  
JACKSON  
 (County)

Located In:

Corner Code 77  
**SURVEY &  
 REMONUMENTATION**

1. Public Land Survey T 2 S R 1 W  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_
2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
 in Section S \_\_\_ T \_\_\_ R \_\_\_
3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
 Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

K-13  
 APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Dean R. Gutekunst in a field survey on 7/30/96 & 9/10 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Hervey Parke, Deputy Surveyor, 1825.  
 W. Oak 11" N  $\frac{1}{2}$  E 58 links (38.28')  
 W. Oak 26" N 75 W 150 links (99.00')  
 No perpetuation found for the 1880's.  
 Not recorded in P.A. 74

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a  $\frac{1}{2}$ " rod in monument box to surface of blacktop of Elm Avenue and Pringle Street.  
 Hand excavation of the area under box did not reveal any additional evidence of original corner. Area is mostly sand fill from former sewer excavations in intersection.  
 Accepted surface rod as the only perpetuation of the original corner.  
 Set a Standard Jackson County Monument to replace rod and buried rod beside monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 T2S, R1W Corner is a 4" diameter X 36" concrete monument with a  $\frac{1}{2}$ " X 36" steel rod and an aluminum cap stamped LS 18658, which is the standard monument for Jackson County.

Northwesterly Southeast corner block foundation house 66.63'  
 Southeasterly Northwest corner, concrete foundation brick entrance, church 57.48'  
 Southeasterly Keystem of fire hydrant 38.84'  
 Northeasterly Stone foundation house (southern two story part) 87.68'  
 West K-1, T3S, R1W (Remonumentation monument) 33.00'

Monument box set over monument to surface of blacktop.

Signed by Dean R. Gutekunst

Date March 1, 1997

Surveyor's Michigan License No. 18658

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

