

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>8</u>	T. <u>2</u> S., R. <u>2</u> E.	E-3, E-4
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>E-4 E 1/4 Cor. Found stone & replaced with 3/4 x 24" pipe on top of stone in 1970 N45°W - 44.93' - 44" W. Oak S32°W - 69.48' - 23" Hickory S62°E - 21.18' - Tele. Pole N21°E - 70.69' - 38" Oak N26°W - 66.96' - 26" Oak</p>	<p>E-3 NE Cor. Found 1" iron rod 6" below surface in 1970 Set R.R. spike on top of iron. N55°E - 29.25' - Twin 10" Oak S36°E - 39.0' - 22" Oak N88°E - 27.1' - 4" iron fence corner post N73°W - 25.79' - 20" Oak S63°W - 49.93' - Power pole</p>
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>E-4 3/4" pipe (Set mon. box) N45°W - 44.93' - 44" W. Oak (stump) S32°W - 69.48' - 23" Hickory S62°E - 21.18' - Tele. pole N21°E - 70.69' - 38" Oak N26°W - 66.96' - 26" Oak</p>	<p>E-3 1" Iron rod (Set mon. box) N55°E - 29.25' - Twin 10" Oak S36°E - 39.0' - 22" Oak N88°E - 27.1' - 4" iron fence corner post N73°W - 25.79' - 20" Oak S63°W - 49.93' - Power Pole</p>
---	---


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell CHIEF OF SURVEY PARTY DATE 10-18-83
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655