

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ S., R. _____ E.		_____
2. PROPERTY CONTROLLING IN SECTION <u>11</u> , T. <u>2</u> N. S., R. <u>2</u> E. W.		2,9
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		_____
5. PRIVATE CLAIMS _____		_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Thomas G. Moran, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- |   |  |
|---|--|
| <p>2. Set midway between N 1/4 corner and NE corner 4"x 36" concrete monument in monument box 1' west <math>\frac{1}{2}</math> of pavement.</p> | <p>9. Set 1"x 8' I.P. with aluminum cap midway between center of section and E 1/4 corner. Center was not set it is a math point only.</p> |
|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| <p>2. 4"x 36" concrete monument.<br/>         N 50° E, 31.59', 16" S. Maple<br/>         N 12° W, 86.38', 24" B. Oak<br/>         N 35° W, 54.07', Power Pole<br/>         S 87° E, 33.00', 4"x 36" concrete monument at R.O.W.</p> | <p>9. 1"x 8' iron pipe with aluminum cap.<br/>         N 57° W, 31.09', 13" Tam.<br/>         N 38° E, 3.25', 7" Tam.<br/>         East approximately 100' to the edge of the swamp.</p> |
|---|--|

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 25860 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_