

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF --: | LOCATED IN --: | CORNER CODE NUMBER |
|--|----------------|--------------------|
| 1. PUBLIC LAND SURVEY <u>11</u> T. <u>2</u> S., R. <u>2</u> E. | | J-3, K-4 |
| 2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____ E. W. | | |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Thomas G. Moran, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


| | |
|---|---|
| <p>J-3 Found old fence corner post with fences going N-S-E-W. Checked distances to government corners east and west. Accepted old fence corner post as corner. Set 4"x 36" concrete monument.</p> | <p>K-4 Found fence corner post with fences going N and W. Checked distances to the N and S government corners. Accepted fence corner as best evidence of 1/4 corner. Set 4"x 3 concrete monument with aluminum cap.</p> |
|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|---|---|
| <p>J-3 4"x 36" Concrete Monument with aluminum cap. S 42° E, 5.70', 15" Maple S 74° E, 50.46', 6" Maple N 03° W, 53.23', 12" Catalpa</p> | <p>K-4 4"x 36" Concrete Monument N 12° W, 6.56', 9" Hickory N 59° W, 33.74', 12" W. Oak S 77° W, 4.05', 16" W. Oak N 45° W, 0.5', Fence Corner Post</p> |
|---|---|

SIGNED BY Thomas G. Moran DATE 5-11-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 25860



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____