

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u>	T. <u>2</u> S., R. <u>2</u> E.	G-6
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>2</u> S., R. <u>2</u> E.	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-6
- W. Oak, S52°W, 64 links
 - Y. Oak 24", N26°W, 104 links
 - Y. Oak 10", S50°W, 51 links
 - Apple 10", N45°W, 101½ links
 - Stone corner and reference stone 1 rod east

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- | | |
|---|---|
| <p>G-6</p> <ul style="list-style-type: none"> Found ½" pinched pipe Dug for stones but didn't find. | <p>7.</p> <ul style="list-style-type: none"> Set 4" concrete monument with aluminum cap #18655 on line and halfway between NE cor. 16 and E½ cor. 16 |
|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>G-6</p> <ul style="list-style-type: none"> N10°E, 12.06', 40" Willow N29°E, 6.39', 20" Willow S57°E, 19.78', 3" Aspen N88°W, 8.33', Fence post Replaced ½" pinched pipe with 1" pipe with plastic cap #18655 | <p>7.</p> <ul style="list-style-type: none"> N49°E, 9.97', 13" B. Oak N11°E, 5.98', 13" B. Cherry N72°W, 22.21', 12" W. Oak N87°E, 18.81', 6" Hickory |
|--|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell CHIEF OF SURVEY PARTY DATE 11-22-77
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655