

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u> T. <u>2</u> S., R. <u>2</u> E.		<u>G-5, G-7</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p>G-5 1" Pipe N10°E, 17.0', 8" Oak N81°W, 14.05', 20" Cherry N80°E, 19.75', 5" Oak S03°W, 9.63', 10" Oak</p>	<p>G-7 1½ Iron Pipe South, 19.94', 32" B. Oak East, 21.09', 13" W. Oak S35 W, 23.12', 13" W. Oak</p>
---	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-5 Found 1" Iron pipe	G-7 Found 1" pipe
------------------------	-------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>G-5 N84°W, 14.25', 26" B. Cherry, PK & tag S08°E, 9.39', 12" R. Oak, PK & tag N12°E, 17.30', 10" W. Oak, PK & tag N79°E, 19.58', 7" R. Oak, Spike</p>	<p>G-7 S80°E, 21.05', 12" Maple S10°W, 19.98', 30" Dead Elm S63°W, 23.18', 13" Maple N53°W, 26.54', 9" Maple Placed ½" pipe with plastic cap #18655 inside 1" pipe</p>
--	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell CHIEF OF SURVEY PARTY DATE 11-22-77
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13655