

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1990**

North 1/4 Corner of Section 26, Napoleon Township

**SURVEY &
REMONUMENTATION**

Chairman Dean R. Whitford
Date Sept. 9, 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 27 1999

For corners in JACKSON Located In: Corner Code #
(County)

SECTION

1. Public Land Survey T 3S R 1E J-9
T _____
T _____
T _____
2. Property Controlling S _____
In Section S _____
3. Miscellaneous S _____
Property in Sec. S _____
4. Lot No. _____ Recorded Plat _____
5. Private Claims _____



2087036
Page: 1 of 1
09/10/1998 11:0
L-1580 P-51

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on August 1, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In 1825, H. Parke - Deputy Surveyor, set a "Post" and recorded two witnesses: "Y. Oak 30, N80° W, 71" (46.86') and "B. Oak 20, S 89° E, 102" (67.32').

In the late 1880's, a Remonumentation Surveyor notes: "Found old stake under stone wall agreeing with the remains of 1st and stump of 2nd Gov't witness. Also witnesses by H F Bean standing. Post under wall stake opposite" and recorded two witnesses: "Y Oak 15 S 87° E, 245 1/2" (162.03') and "Hickory 10 N 89° W 516 1/2" (340.89').

Not recorded under PA #74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found vertical Fire Clay (FC) in 3 pieces with a 1" iron pipe (IP) on North side. Large stones around FC may have been old stone wall. Accepted found FC as a careful and faithful perpetuation of the original corner. Replaced FC with a standard concrete monument. Set FC pieces and IP on North side of monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 36" long concrete monument with cap stamped "J-9, T3S-R1E, LS #29245, 1997".

South	Set nail and tag #29245, East side 10" Black Walnut	9.54'
S 65° W	Set nail and tag #29245, Southeast side 18" Oak	15.40'
S 13° W	Set nail and tag #29245, East side 8" Pine	29.72'
S 76° E	Set nail and tag #29245, North side 13" Triple Oak	60.87'
South	County Surveyor sign post	2.0'

Note: Bearings are magnetic.



Signed by David Erickson Date 9-8-98

Surveyor's Michigan License No. 29245

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN, 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983