

Chairman Don J. [Signature] NW CORNER OF SECTION 31, SUMMIT TWP.

Date Dec. 20, 1994

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 JACKSON COUNTY
 RECORDED

For corners in

_____ Jackson _____ Located In: _____ Corner Code # _____

1. Public Land Survey T _____ R _____
 T 3S R 1W _____ A-11
 T _____ R _____
 T _____ R _____ **SURVEY &**

2. Property Controlling S _____ T _____ R _____ **REMONUMENTATION**
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____ **MAY 03 1995**

30 DEC 94 11:23 A.M.

GERALD J. McDEVITT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat COMMISSION
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, _____, in a field survey on _____, 19 _____, and by certificate over requirements of P.A. 74, Michigan Act 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11 - Original survey by Harvey Parke DS in 1825. He intersected Range line .18 chains S. cor. With witness:
 8" W. Oak -N17°E- .21 (chains) 8" Oak -S12°E- .13 1/2 (chains)
 County Surveyor Records show in a survey by H.F. Bean in 1886, that he set a fireclay post as the corner. With Witnesses:
 18" Br. Oak -East- 105 (links)(69.30')
 8" Br. Oak -N84°W- 126 1/2 (links)(83.49')
 Noted: "stake standing and found remains of one witness"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

\$ 2.00 REMONUMENTATION
 \$ 7.00 CORNER REMONUMENTATION

Section 31, Summit Township

A-11 - Found fireclay 8" below surface with top 1/3 broken off, found 3/4" pipe at South edge of fireclay- accepted fireclay as a careful and faithful reestablishment of the position of the original corner. dug down 3' and found broken pieces of stone, but no brick, replaced fireclay with Standard Jackson County Monument, and placed fireclay on North side of monument. Closing corner is 11.88' South of Standard Corner.
 (NEAR INTERSECTION OF FENCE LINES EAST-WEST AND NORTH-SOUTH)
 (CLOSING CORNER IS ON RANGE LINE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 (NW corner of Section 31)
 Jackson County Monument

Witness sign post set -South - 1.3'
 Nail & tag #13039 E. side 14" Cherry - N05°E- 16.33'
 Nail & tag #13039 S. side 20" Cherry - N85°W- 16.31'
 Nail & tag #13039 N. side 7" Cherry -S80°E- 26.28'
 Nail & tag #13039 W. side 18" Cherry -S25°W- 9.68'
 (STANDARD CORNER IS NORTH 11.88')

*Standard Jackson County Monument is a 1/2" iron rod 36" long with a Jackson County Remonumentation disk encased in a 4" concrete cylinder.

Signed by Arden S. Pierson Date December 6, 1994

Surveyor's Michigan License No. 13039

