

WEST 1/4 POST SECTION 25
 EAST 1/4 POST SECTION 26
 SUMMIT TOWNSHIP

SURVEY &
 REMONUMENTATION

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Jackson Located In: Corner Code #
 (County)

SECTION

- 1. Public Land Survey T 3 S R 1 W K-10
- 2. Property Controlling in Section S ___ T ___ R ___
- 3. Miscellaneous Property in Section S ___ T ___ R ___



2139379
 Page: 1 of 2
 12/08/1999 11:41A
 L-1618 P-1233

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Timothy B.

I, VanGieson, in a field survey on October 31, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-10: Original government survey dated February 12, 1825. "40.00 ch. (2,640.00') set 1/4 Section Post." "Wood Post" Yellow Oak 12" S 46° E 18 lks. (11.88') Yellow Oak 12" N 69-1/2° W 21 lks. (13.86') Hervey Parke (Deputy Surveyor) May 04, 1825
- K-10: Remonumentation survey dated 1886 "Fire Clay" "Established this corner." H.F. Bean 1886 Hickory 10" N 33° W 76 lks. (50.16') Hickory 16" S 25° E 26 lks. (17.16')
- K-10: See back for additional supporting documentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- K-10: Found fire clay in monument box. Excavated at this position and found fire clay to be the bottom 16-1/2". Also found brick memorial South of fire clay at a depth of 1.0'.

Accepted fire clay as faithful and careful perpetuation of Corner K-10.

Set standard Jackson County Remonumentation "Harrison" monument in place of fire clay. Left fire clay 0.4' South of Harrison monument at a depth of 1.5'±.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-10: 4" x 30" Harrison Monument with brass cap R.L.S. 24621
- N 29° E 60-d in Northwest side 20" Oak 59.49'
- N 57° E 60-d in North side 20" Oak 33.17'
- N 90° E Sign post 33.0'±
- S 84° E 60-d in twin 16" Oak 37.13'
- S 56° W N.E. Corner House No.5500 100.82'
- N 79° W 60-d in South side 24" Oak 115.69'



Signed by Timothy B. VanGieson

Date November 22, 1999

Surveyor's Michigan License No. 24621

A (continued)

Source: P.A. 74 recorded in Liber 1 Page 421 by Richard E. Gutekunst Registered Land Surveyor 7863.

Date: July 12, 1972

"Found iron in monument box 3 to 4'± south of centerline of Marion Road 1'± east of centerline of Draper Road pavement."

Item A

Hickory 10" N-33°-W 50.16', 76 links

Hickory 16" S-25°-E 17.16', 26 links

Item B

Found by Fred C. Riley from witnesses September 3, 1920, Gone July 1972

Item C

Found iron in monument box 3 to 4'± south of centerline of Marion Road 1'± east of centerline of Draper Road pavement

N 30°± E - 17" oak - 58.97' - fence east

East double oak - 36.87'

S 25°± E - 24" hickory 89.93'

Source: Certificate of Survey by Timothy B. VanGieson Registered Land Surveyor No.24621

Date: September 19, 1979

"Found fire clay in monument box."

16 nail & tag in 24" Oak N 25° E 58.95'

16 nail & tag in 24" Oak N 65° E 32.45'

20 nail & tag in twin 12" Oak N 90° E 36.80'

16 nail & tag in power pole N 45° W 50.80'

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION



Mindy Reilly - Jackson Co.

CORREN

2139379

Page: 2 of 2

12/08/1999 11:41A

L-1618 P-1233