

SOUTH 1/4 POST SECTION 24
 NORTH 1/4 POST SECTION 25
 SUMMIT TOWNSHIP

SURVEY &
 REMONUMENTATION

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Jackson Located in: Corner Code #
 (County)

1. Public Land Survey T 3 S R 1 W L-9
 T _____
 T _____
 T _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____



2139381
 Page: 1 of 2
 12/08/1999 11:41A
 L-1618 P-1235

Register of Deeds Stamp & rite Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Timothy B. VanGieson, in a field survey on October 29, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-9: Original government survey dated February 12, 1825. "39.84-1/2 ch. (2,629.77') set post on true line."
 "Wood Post"
 White Oak 24" S 89° E 58-1/2 lks. (38.61')
 White Oak 30" S 66° W 35 lks (23.10')
 Hervey Parke (Deputy Surveyor)
 May 04, 1825
- L-9: Remonumentation survey dated 1886
 Corner unknown
 White Oak 34" S 88-1/2° E 57 lks. (37.62')
 Maple 2" N 17-1/4° E 46-1/2 lks. (30.69')
 Fire clay 1-1/2 rods (24.75') North
 "Post out. One good witness left found remains of other."
 H.F. Bean 1886
- L-9: See back for additional supporting documentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-9: Found Fisher's accessory trees. White Oak now 34" and Maple now 16"± stump. Also found sandstone with brick pieces 24.75'± North. Dug 2.2' (East-West) x 2.0' (North-South) hole in asphalt based on Fisher's accessory distances. Found intact fire clay at a depth of 2.4'. Also found brick memorials starting at a depth of 4' and ending at 5'. Fire clay is 6.98' South and 0.89' West of corner recorded in Liber 2 Page 632.

Accepted fire clay as faithful and careful perpetuation of corner established by H.F. Bean in 1886.

Set standard Jackson County Remonumentation "Harrison" monument. Left fire clay below Harrison monument at a depth of 3.3'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-9: 4" x 30" Harrison Monument with brass cap R.L.S. No.24621
 N 05° E Sign post 26'± (behind pointed sandstone)
 N 05° E Pointed sandstone witness corner 24.70'
 N 53° E 60-d in Southeast side 19" Oak 61.40'
 N 72° E 60-d in North side 27" Oak 98.50'
 S 37° E 60-d in Northeast side 34" Oak 25.26'
 S 19° W 60-d in East side 9" Oak 29.46'
 N 05° W 60-d in East side 21" Oak 34.84'



Signed by Timothy B. VanGieson

Date November 21, 1999

Surveyor's Michigan License No. 24621

A (continued)

Source: Frank A. Fisher Registered Land Surveyor No.3102

Date: November 1924

"Found fire clay post at corner in road from witnesses. Could not find fire clay post 1-1/2 rods North, but found a stone 2.0' long which had been set in its place with brick around."

White Oak 11" S 40° E 24.45'

Maple 23" N 17-1/4 E 29.8'

Source: J. Gawlak (not registered)

Date: 1930

"O.K. In Line of Fence South and North."

Source: P.A. 74 recorded in Liber 2 Page 632 by Douglas W. Hooth Registered Land Surveyor No.7966.

Date: June 03, 1977

"Found 3/4" Iron pipe with bashed Top in Floyd Road E & W."

S-10-E 30.25' 29" Oak

South 27.58' Wood Corner Fe. Post

N-20-W 28.20' 8" Oak



2139381
Page: 2 of 2
12/08/1999 11:41R
L-1618 P-1235

Mindy Reilly - Jackson Co.

CORREN

**SURVEY &
REMONUMENTATION**

MAR 13 2000

SECTION