

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 343 of 1996**

Chairman *Dean Stalton* East 1/4 Corner of Section 32, Napoleon Lake Township
LAND CORNER RECORDATION CERTIFICATE
 Date *Nov 18, 1998* Filing Requirement of Act 74, Mich. P.A. 1970

For corners in JACKSON Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T3S R2E E-12
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____



2093598
 Page: 1 of 1
 11/20/1998 03:26P
 L-1586 P-914

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on May 28, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Around 1824, H. Parke - Deputy Surveyor, reported the corner as "Set Post" and recorded two witnesses: "W. Oak 16, S56°W, 8" (5.28') and "Y. Oak 10, S64 1/2°E, 28" (18.48').

In the late 1800s, the Remonumentation Surveyor reported "Found fireclay post at corner set for Norvell" and recorded three witnesses: "Y. Oak 15, S26°E, 80 1/2" (Norvell Witness)(53.13)', "Y. Oak 24, S64 1/2°W, 7" (Norvell Witness)(4.62') and "Y. Oak 8, N54°E, 26" (17.16').

This corner not recorded under Public Act #74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Fire Clay (FC) with brick pieces surrounding the base. Accepted found FC as a careful and faithful perpetuation of the position of the original corner. Replaced FC with a standard Jackson County Concrete Monument. Buried FC on North side of monument. Fences run East, West and North from corner. A railroad tie fence post is on South side of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 36" concrete monument with metal rod and standard aluminum cap stamped "E-12, T3S-R2E, 1997, LS #29245".

N 22° E	Set nail and tag #29245, South side 18" Hickory	26.28'
N 46° E	Set nail and tag #29245, South side 17" Hickory	46.66'
S 28° W	Set nail and tag #29245, East side 12" Oak	45.72'
S 79° W	Set nail and tag #29245, North side 28" Oak	4.92'
East	County Surveyor sign post	1.5'

NOTE: Bearings are magnetic.



Signed by *David Erickson* Date 11-18-98

Surveyor's Michigan License No. 29245

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993