

JACKSON COUNTY  
APPROVED LAND CORNER  
P.A. 343 of 1999

Chairman *Mark J. Johnson*  
Date Nov. 10, 1999

NORTH 1/4 CORNER SECTION 3  
SPRING ARBOR TOWNSHIP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

MAR 18 2000

For corners in

<u>JACKSON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>2W</u>	<u>H-1</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>



2136078  
Page: 1 of 1  
11/24/1999 02:42P  
L-1618 P-15

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID L. CLIFFORD, in a field survey on JULY 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. POST NOT SET IN ORIGINAL SURVEY.
2. FOUND NO EVIDENCE THAT CORNER HAD EVER BEEN SET.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED IN GENERAL LOCATION OF CORNER ALONG FENCE FROM THE SOUTH AND FENCE FROM THE WEST. FOUND 3/4" PIPE IN SIDE OF A 4" PIPE AT THE SOUTH 1/4 CORNER OF SECTION 34, T2S, R2W, 42' WEST OF NORTH-SOUTH FENCE AND 8' SOUTH OF EAST WEST FENCE. DID NOT FIND ANY EVIDENCE OF CORNER. SET 3/4" X 36" ALUMINUM PIPE MONUMENT IN SATURATED GROUND ON STANDARD LINE 1/2 WAY BETWEEN SECTION CORNERS (BOTH OF WHICH ARE FIRE CLAYS). MEASURED WEST 2641.73' TO G-1. MEASURED EAST 2641.73 TO I-1. CORNER IS 8' SOUTH OF FENCE TO WEST AND 5' EAST OF FENCE TO SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-1 T3S R2W
- 3/4" X 36" ALUMINUM PIPE MONUMENT & JACKSON COUNTY ALUMINUM CAP STAMPED 25837
  - NAIL & TAG 25837 NE CORNER RR TIE FENCE POST, N51°W, 9.86'
  - NAIL & TAG 25837 EAST SIDE 13" HICKORY, N38°W, 18.85'
  - NAIL & TAG 25837 WEST SIDE 20" ASH, N39°W, 25.86'
  - 60D SPIKE NE SIDE 16" HICKORY, S48°W, 13.56'
  - 3/4" PIPE IN 4" PIPE H-13 T2S, R2W, WEST, 47.03'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by *David Clifford*

Date NOVEMBER 10, 1999

Surveyor's Michigan License No. 25837