

APR 07 1998

JACKSON COUNTY APPROVED LAND CORNER P.A. 345 of 1990

Chairman [Signature] Date Nov. 15, 1997

EAST 1/4 POST, SECTION 23, SPRING ARBOR TOWNSHIP LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

#2053273 Liber 1555 Page 77 Page 1 of 1 Jackson Co., MI Recorded 11/14/1997 01:47P Mindy Reilly Register of Deeds

For corners in

Table with columns: Jackson (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number. Includes handwritten 'P8 769' and a rectangular stamp area.

4. Lot No. , Recorded Plat 5. Private Claims

I, Michael A. Groat, in a field survey on November 7, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (8, J) contains a circle with a dot.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey in 1825 by Lucius Lyon, Deputy Surveyor; set post, Hick, 7", S76°W, 21 Lks, B. Oak, 18", N40°E, 52 Lks.

H.F. Bean, 1886, Found stone and 1 witnesses, set post and a stone 2 rods East and 2 rods West. W. oak, 30", N71-1/2°E, 83 Lks; W Oak, 30", N17°E, 119 Lks.

Harold Dorcy, P.S. #9429, in 1972, found monument box, gives nothing else.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" pipe in monument box, 2.5 feet West of centerline and in line with fence East. Excavated and found fireclay 1 foot down. Also found stones 2 rods East and 2 rods West. Accepted the fireclay as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner is a 4"x36" standard Jackson County concrete monument with corner code, Township and License number stamped on the cap.

Witnesses table with columns: Direction, Description, Distance. Includes entries for S30°W, N23°E, N45°W, S31°E, and East.



Signed by [Signature] Surveyor's Michigan License No. 39079

Date November 11, 1997