JACKSON COUNTY APPROVED LAND CORNER P.A. 345 of 1999 NE CO	DRNER OF SECTION 35, SPRIN	IG ARBOR TWP. IBER
Pate Dec. 20, 1991 For corners in Jackson	LAND CORNER RECORDATION (Filing Requirement of Act 74, Mi	- -
1. Public Land S. T. Property Controlling S T in Section S T 3. Miscellaneous S T	Corner Code	TATION GERALD J. McDEVITT REGISTER OF DEEDS Register of Deeds Stamp & File Number
4. Lot No, Recorded Plat 5. Private Claims		A B C D E F G H I J K L
Arden S. Pierson PS, in a field sur do hereby certify that under requirements of P. in lines 1 and 2 above were in conformance	A. 74, Michigan P.A. of 1970, the corner points with regulations and rules therefore as requ	smentioned 6 18 17 16 15 14 13
current manual of survey instructions of the U Management or by a decree of a Court of Law a above were in conformance with the rules of the Court of Law; established, re-established, expressed below: NOTE: Not more than 4 corners, all in the	and/or that the corner points mentioned in line he Michigan Board of Land Surveyors or by a E monumented, re-monumented, recovered,	es 3, 4 and 5 Decree of a , found as 8 19 20 21 22 23 24 9 10 30 29 28 27 26 25
records show he s 20" Hickory -S84 County Surveyor s dated May-June,	y by Lucius Lyon DS, 182 set a post as the corner °W- 71 links 10" Hickorecords also show in a s 1886, that he set a Fire Elm -S07°W- 248 1/2 linwhite Oak -N33°E- 88 li	r with witnesses: ory -S84°E- 24 links survey by H.F. Bean, e Clay post with
B. Description of corner evidence found	•	
Section	on 25, Spring Arbor Town	nship
K-11 - Found pinched pipe with unreadable cap. Dug down and found Fire Clay surrounded by brick 1.3' below surface - And accepted as a careful and faithful perpetuation of the position of the original corner. Replaced Fire Clay with Standard Jackson County Monument and placed Fire Clay on the North side of the monument. ARDEN S.		
Witness sign p Nail & tag #13 Nail & tag #13 Nail & tag #13 Nail & tag #13	and accessories established to perpetual 11 (SW corner of Section Jackson County Monument cost set -East- 30.0' 3039 NE side 35" Oak -N2 3039 NW side 52" Oak -N3 3039 N. side 7" Elm -S75 3039 SW side 38" Oak -S5 physical Road centerline	20°W- 73.26' 35°E- 59.18'* 5°W- 25.32' 50°E- 45.50'
*Standard Jackson County Remonu	nty Monument is a 1/2" i umentation disk encased) UUT	iron rod 36" long with a in a 4" concrete cylinder. November 1, 1994

13039

Surveyor's Michigan License No. _

SW CORNER OF SECTION 25, SPRING ARBOR TOWNSHIP

Certification by H.F. Bean (page 620, GLO Notes) "post set are fireclay, three inches in diameter and two feet long"

Recorded in Liber 2, page 201, by Richard E. Gutekunst PS #7863, dated July 11, 1973. "Found fireclay 8" down iron to surface." With Witnesses:

44" W. Oak -N36°E- 58.50' 13" Hickory -S70°E- 38.32'

26" Oak -N16°W- 72.95'

NE cor. house foundation #6230 -N48°W- 104.65' Used in survey recorded in Liber 861, page 1281, dated July 11, 1973.