

**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 345 of 1990**  
**CENTER OF SECTION 36, SPRING ARBOR TWP.**

Chairman Arden S. Pierson  
 Date Dec. 10, 1994

LIBER 1451 PAGE 184

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 JACKSON COUNTY  
 RECORDED

For corners in  
Jackson  
 (County)

Located In: Corner Code L-12

- |                                    |                         |                        |
|------------------------------------|-------------------------|------------------------|
| 1. Public Land Survey              | T <u>3S</u> R <u>2W</u> | <u>L-12</u>            |
|                                    | T _____ R _____         |                        |
|                                    | T _____ R _____         | <b>SURVEY &amp;</b>    |
|                                    | T _____ R _____         | <b>REMONUMENTATION</b> |
| 2. Property Controlling in Section | S _____ T _____ R _____ |                        |
|                                    | S _____ T _____ R _____ |                        |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | <u>MAY 03 1995</u>     |
|                                    | S _____ T _____ R _____ | <b>COMMISSION</b>      |

30 DEC 94 11:21 A.M.

GERALD J. McDEVITT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35								
13													

Arden S. Pierson PS, in a field survey on November 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-12 - This position not established by original government surveyors.

\$ 2.00 REMONUMENTATION  
 \$ 7.00 CORNER REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Section 36, Spring Arbor Township**

L-12 - Intersected lines from opposite quarter-section corners - falls in physical centerline of road, in line with occupation lines North and South.  
 Set standard Jackson County Monument at corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-12 (Center of Section 36)  
 Jackson County Monument

- Witness sign post set - North - 30.0'
- Nail & tag #13039 in NW side power pole - N78°E - 118.98'
- Nail & tag #13039 in W. side Twin 6" Elm - N30°E - 39.28'
- Nail & tag #13039 in SW side 14" Oak -S35°E- 42.71'
- Nail & tag #13039 in NW side 17" Ash -S65°W- 70.80'

\*Standard Jackson County Monument is a 1/2" iron rod, 36" long with a Jackson County Remonumentation disk, encased in a 4" concrete cylinder.  
 November 1, 1994



Signed by Arden S. Pierson Date \_\_\_\_\_

Surveyor's Michigan License No. 13039