

**JACKSON COUNTY
APPROVED LAND CORNER**

P.A. 343 of 1990
 ACTING Chairman David E. Eubank
 Date 7-5-97

SOUTHWEST CORNER, SECTION 36
 COLUMBIA TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2040569
 Liber 1546 Page 465
 Page 1 of 2
 Jackson Co., MI
 Recorded
 07/09/97 01:16P
 Mindy Reilly
 Register of Deeds

For corners in
JACKSON
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|------|
| 1. Public Land Survey | T <u>4</u> S R <u>1</u> E | K-13 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |

**SURVEY &
 REMONUMENTATION**
APR 07 1998
SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

DEAN R. GUTEKUNST, in a field survey on Sept. 24, 1996 & May 19, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original Government Post set by Benjamin Hough, Deputy Surveyor, 1815.
 B. Oak 12" N 44 1/2° W 14 links (9.24')
 B. Oak 10" S 60° E 92 links (60.72')
 Perpetuation by H. F. Bean, no date.
 * Maple 8" S 81 1/4° W 214 1/2 links (141.57')
 Hickory 10" N 62° E 54 links (35.64')

Stone Corner

Continued on back,

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found Stone, with iron on East side and 4.15' West of iron for the Northwest corner of Section 1, T5S, R1E.

Stone is 2.3'± long and approximately 12" wide.

Backhoe excavation, 9/24/1996, of a 3' X 10' X 5' deep area, did not reveal additional information. Reset stone, with brick around and old iron on South side, 4' below existing gravel surface.

Accepted the Stone as a careful and faithful perpetuation of the position original corner, as remonumented by Bean.

Set a Standard Jackson County Monument to replace the Stone, 5/19/1997.



2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 T4S. R1E Corner is a 4" diameter X 30" Cast Iron Harrison monument with a brass cap stamped LS 18658, which is a standard monument for Jackson County.

- ** N 30° W 15" Oak 68.35' 40d and washer on Southwest side.
- *** S 20° W 24" Maple 66.08' 40d and washer on West side.
- S 50° W Northwest corner of concrete foundation of House # 12986 134.13'
- N 45° E Southeast corner of concrete foundation of House # 12901 202.80'
- S 60° E PK nail in a lead plug and "X" cut on top of a large rock 53.85'

Monument box set by Jackson County Road Commission

igned by Dean R. Gutekunst
 18658

Date July 1, 1997

urveyor's Michigan License No. _____

- Record 3605