

JACKSON COUNTY
APPROVED LAND CORNER

P.A. 343 of 1996
 Acting Chairman David E. Eubank
 Date 7-9-97

SOUTH 1/4 POST, SECTION 36
 COLUMBIA TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2040670
 Liber 1546 Page 466
 Page 1 of 2
 Jackson Co., MI
 Recorded
 07/09/97 01:17P
 Mindy Reilly
 Register of Deeds

For corners in	Located In:	Corner Code #
JACKSON (County)		
1. Public Land Survey	T 4 S R 1 E	L-13
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

DEAN R. GUTEKUNST Sept. 25, 1996 & May 19, 1997
 in a field survey on _____, 19____

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- Original Government Post set by Benjamin Hough, Deputy Surveyor, 1815.
 - Hickory 16" S 18 1/2 E 12 links (7.92')
 - Hickory 11" N 3 W 15 links (9.90')
- Perpetuation by H. F. Bean, no date No description.
 - Elm 30" N 13 1/2 W 91 links (60.06')
 - Elm 30" N 46 1/2 W 80 links (52.80')

Continued on back,

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Blue Stone with iron on North side. Stone is 4" X 7" X 15" long.
 Backhoe excavation, 9/25/1996, of a 3' X 10' X 6' deep area, did not reveal additional information. Reset stone to 3' to 4' below existing gravel surface.
 Corner is 1'± North of center line of Taylor Road (blacktop- May 1997).
 Accepted the Stone as a careful and faithful perpetuation of the position of the original corner.
 Set a Standard Jackson County Monument to replace the stone, May 19, 1997.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 T4S, R1E Corner is a 4" diameter X 30" Cast Iron Harrison monument with a brass cap stamped LS 18658, which is a standard monument for Jackson County.

- * S 25°W 10" Hickory 27.85' 40d and washer on West side.
 - N 60°E 12" Hickory 86.00' 40d and washer on North side.
 - ** N 45°W 39" Oak 63.65' 40d and washer on South side.
 - *** N 60°W 23" Hickory 72.89' 40d and washer on South side.
 - S 45°E 26" Maple 58.07' 40d and washer on Northeast side.
 - N 20°E 11" Ash 41.79' 40d and washer on East side.
 - North Steel post and survey marker sign attached 25.00'
- Monument box set by Jackson County Road Commission.



ned by Dean R. Gutekunst Date July 1, 1997
 Surveyor's Michigan License No. 18658

Record 366